

35 TECHNOLOGY DRIVE
WARREN, NJ 07059
908.668.7777
FAX 908.754.5936
www.whitestoneassoc.com

February 5, 2015

via email

#### THE HAMPSHIRE COMPANIES, LLC

22 Maple Avenue Morristown, New Jersey 07960

Attention:

Eric Helstrom, AIA, LEED AP

Senior Project Manager

Regarding:

PRELIMINARY GEOTECHNICAL INVESTIGATION &

STORMWATER MANAGEMENT AREA EVALUATION

PROPOSED MOUNTAINSIDE HOSPITAL REDEVELOPMENT

ONE BAY AVENUE

BLOCK 4215, LOT 1 AND BLOCK 106, LOTS 15, 35 & 39

TOWNSHIP OF MONTCLAIR & BOROUGH OF GLEN RIDGE,

**ESSEX COUNTY, NEW JERSEY** 

WHITESTONE PROJECT NO.: GJ1413224.000


Dear Mr. Helstrom:

Whitestone Associates, Inc. (Whitestone) has completed a preliminary geotechnical investigation and stormwater management (SWM) area evaluation at the above referenced site. The results of the limited evaluation and preliminary recommendations presented below are based on the soil conditions disclosed from a limited number of borings and test pits performed during Whitestone's field investigation. Recommendations for further investigation also are included herein.

The purpose of the preliminary subsurface soils investigation was to assess anticipated geologic features, shallow groundwater and/or estimated seasonal high groundwater, existing fill, and the potential feasibility of shallow foundations and/or expected earthwork requirements. While the scope of this preliminary investigation will not be sufficient to formulate detailed design recommendations and a more comprehensive geotechnical investigation ultimately will be required, this preliminary investigation may be used to assess potentially development impactive geotechnical issues to support preliminary studies regarding the feasibility of developing the property.

#### 1.0 SUMMARY OF FINDINGS

In general, the subsurface conditions preliminarily indicate conditions suitable for shallow foundation design. The exploration indicated the presence of cobbles and boulders and areas of moisture-sensitive soils that will impact the planned construction. Based on past experience, earthwork activities will require soil moisture control efforts. Excavation difficulties due to the presence of cobbles and boulders are expected at depths as shallow as eight feet below ground surface (fbgs) which may impact the installation of deeper foundations and utilities. Depending on the time of year of construction, site work should anticipate overexcavation of moisture sensitive soils in structural areas, using mechanical and/or chemical subgrade stabilization techniques, and exercising detailed attention to construction methods while maintaining strict moisture control. In addition, existing fill materials containing variable amounts of objectionable debris were encountered to a depth of up to four feet that will require overexcavation below foundations.





#### 2.0 PROJECT DESCRIPTION

#### 2.1 Site Location and Existing Conditions

The subject site is located at One Bay Avenue in the Township of Montclair and the Borough of Glen Ridge, Essex County, New Jersey and is further identified as Block 4215, Lot 1 and Block 106, Lots 15, 35 and 39. The site currently is developed with a one- and three-story medical/education masonry building within the Mountainside Hospital complex with associated pavements, courtyard, concrete walkways, landscaping and utilities. The building has a full depth basement with variable heights. At the time of Whitestone's preliminary investigation, the building was observed to be in good structural condition. The existing building occupied the majority of the proposed building footprint. The existing pavements were observed to be in fair structural condition with areas of cracking, potholes and patches. At the time of Whitestone's investigation, the subject site was serviced aboveground by electric, cable and telephone lines and underground by electric, telephone, cable, fiber optic, water, natural gas, stormwater and sanitary sewer lines.

The site is bound to the north by Roswell Terrace followed by residential buildings; to the west by Walnut Crescent followed by residential buildings; to the east by residential buildings followed by Sherman Avenue; and to the south by Bay Avenue followed by Mountainside Hospital. Based on the September 16, 2014 *Boundary & Topographic Survey* prepared by Control Point Associates, Inc., the subject property has an elevation change of approximately 15 feet across the site. More specifically, the area of the proposed building has an elevation change of approximately one foot to two feet.

#### 2.2 Site Geology

The subject property is situated within a section of the Piedmont Physiographic Province known as the Newark Basin. Specifically, the subject site is underlain by the Lower Jurassic and Upper Triassic Sandstone and Siltstone facies of the Passaic Formation, which is part of the Brunswick Group. The formation generally consists of interbedded grayish-red to brownish-red medium-grained to fine-grained, medium-bedded to thick-bedded feldspathic sandstone, and brownish-red to purplish-red, coarse-grained siltstone.

The overburden materials at the site include Rahway Till associated with the Wisconsinan Glacier that presumably reached its most southerly advance approximately 20,000 years ago and ended approximately 10,000 years ago. The glacial deposits are expected to overlay the weathered rock. Glacial till in the area typically contains a heterogeneous mixture of sand, silt, clay and gravel mixed with variable amounts of boulders and cobbles. Overburden materials also include man-made fill associated with past and present development of the subject site.

#### 2.3 Proposed Construction

Based on the September 17, 2014 (last revised September 24, 2014) Concept A and Conceptual Grading A plans prepared by Bohler Engineering NJ, LLC (Bohler), the proposed redevelopment will include demolition of the existing buildings and construction of a three-story, approximately 20,000 square feet footprint medical building with a finished floor elevation of 251.90 feet above mean sea level (msl), trash enclosure and associated new pavements, landscaping and utilities. The proposed building is not anticipated to have any below-grade levels at this time. Final details of the proposed building structural loads, column spacing, and floor loads were not developed at the time of this report. Based on past experience with similar facilities, Whitestone anticipates that maximum column loads will be less than 300 kips. Based on existing and proposed grades, Whitestone the site will be redeveloped at or near existing site elevations with maximum cuts and fills on the order of three feet to five feet; with the exception of the existing basement.



#### 3.0 FIELD INVESTIGATION & LABORATORY TESTING

#### 3.1 Fieldwork

Field exploration at the project site was conducted by means of six soil test borings (identified as B-1 through B-6) performed with a truck-mounted drill rig using hollow stem augers and split-spoon sampling techniques and five soil profile pits (identified as SPP-1 through SPP-5) performed with a rubber-tire backhoe. Borings B-1 through B-4 were performed near the proposed building footprint to depths of ranging from 13.5 fbgs to 24.3 fbgs. Borings B-5 and B-6 were performed within proposed pavement areas to depths of five fbgs and six fbgs, respectively. Profile pits SPP-1 through SPP-5 were performed within or near proposed SWM areas to depths ranging from eight fbgs to 13.0 fbgs. Soil borings and test excavations subsequently were backfilled to the surface with excavated soils from the investigation and borings were surficially restored with asphaltic pavement cold patch, as necessary. The locations of the tests are shown on the accompanying *Test Location Plan* included as Figure 1. *Records of Subsurface Exploration* are provided in Appendix A.

The soil borings and profile pits were conducted in the presence of a Whitestone engineer who performed field tests, recorded visual classifications, and collected samples of the various strata encountered. The borings and profile pits were located in the field using normal taping procedures and estimated right angles. These locations are presumed to be accurate within a few feet.

Soil borings and Standard Penetration Tests (SPTs) were conducted in general accordance with ASTM International (ASTM) designation D 1586. The SPT resistance value (N) can be used as an indicator of the consistency of fine-grained soils and the relative density of coarse-grained soils. The N-value for various soil types can be correlated with the engineering behavior of earthworks and foundations.


Groundwater level observations, although not encountered, were recorded during and immediately after the completion of field operations prior to backfilling the borings. Seasonal variations, temperature effects, man-made effects, and recent rainfall conditions may influence the levels of the groundwater, and the observed levels will depend on the permeability of the soils. Groundwater elevations derived from sources other than seasonally observed groundwater monitor wells may not be representative of true groundwater levels.

#### 3.2 Laboratory Testing Program

Representative samples of a selected strata encountered were subjected to a laboratory testing program that included Atterberg limits determinations (ASTM D-4318), moisture content determinations (ASTM D-2216) and washed gradation analyses (ASTM D-422) in order to perform supplementary engineering soil classifications in general accordance with ASTM D-2487. The soil stratum tested was classified by the Unified Soil Classification System (USCS) and results of the laboratory testing are summarized in the following table. Quantitative test results are provided in Appendix B.

	PHYSICAL/TEXTURAL ANALYSES SUMMARY											
Boring Sample Depth (fbgs) % Passing No. 200 Content (%) Liquid Limit Plastic Index Classification												
B-1	S-3	5.0 - 7.0	32.9	10.1	NP	NP	SM					
B-2	S-2	3.0 - 5.0	57.6	15.0	25	6	CL-ML					
B-2	S-6	18.0 - 20.0	21.4	6.3	NP	NP	SM					

NP - Non Plastic





#### 4.0 SUBSURFACE CONDITIONS

The subsurface soil conditions encountered within the tests consisted of the following generalized strata in order of increasing depth. *Records of Subsurface Exploration* are provided in Appendix A.

**Surface Materials:** The tests were performed within either existing paved areas or grass-covered areas. The borings performed within existing paved areas encountered approximately 2.5 inches to four inches of asphaltic concrete pavement at the surface underlain by approximately 2.5 inches to four inches of gravel subbase materials. The tests performed within existing grass-covered areas encountered approximately three inches to nine inches of topsoil at the surface.

**Existing Fill Materials (Stratum 1):** Beneath the surface cover, the majority of the tests encountered existing fill materials that consisted generally of silty sand with variable amounts of gravel and debris. The debris encountered consisted of coal, cinders, brick and metal. Where encountered, the existing fill materials extended to depths ranging from one fbgs to four fbgs. SPT N-values within the existing fill materials ranged between nine blows per foot (bpf) and 23 bpf, and averaged approximately 13 bpf.

Glacial Deposits (Stratum 2): Underlying the surface cover and/or existing fill materials, the tests encountered natural glacially deposited soils generally consisting of: silty sand (USCS: SM) with variable amounts gravel, cobbles and boulders or silt (USCS: ML) with variable amounts of sand and gravel. The tests were terminated within the glacial deposits at depths ranging from five fbgs to 24.3 fbgs. SPT N-values within coarse-grained portions of this stratum ranged between 10 bpf and refusal (refusal defined as greater than 50 blows per six inches of split-spoon sampler penetration), generally indicating medium dense to very dense relative density and averaging approximately 36 bpf. Pocket penetrometer tests performed within fine-grained portions of this stratum resulted in unconfined compressive strengths ranging between approximately 0.5 ton per square foot (tsf) and two tsf, generally indicating medium stiff to very stiff consistency.

Groundwater: Groundwater was not encountered within the tests performed with the maximum depth explored of 24.3 fbgs, corresponding to elevation 229.7 feet above msl. Perched groundwater may be encountered above the impermeable fine-grained site materials throughout the site, especially following precipitation events. Seasonal variations, temperature effects, and recent rainfall conditions may influence the levels of the groundwater. Groundwater elevations derived from sources other than seasonally observed groundwater monitor wells may not be representative of true groundwater level.

#### 5.0 CONCLUSIONS AND PRELIMINARY RECOMMENDATIONS

The following discussion is based on the subsurface conditions encountered during Whitestone's limited subsurface investigation for the proposed development and is intended to provide general characteristics of the subsurface conditions for preliminary planning purposes and should not be utilized for final design of structural foundations, floor slabs, or pavements. These preliminary considerations and site development options should be confirmed or revised upon development of the project design concept and completion of a site-specific subsurface investigation and engineering analyses.

**Foundations:** Whitestone preliminarily anticipates that moderately-loaded structures may be supported on conventional spread and continuous wall footings following overexcavation of existing fill materials if encountered at or below proposed foundation bearing elevations. Foundations may be designed to bear either within the on-site natural soils or controlled structural fill, provided these materials are properly evaluated, placed, compacted, and prepared in order to control their moisture content. Foundations bearing within these materials may be designed to impart a maximum allowable net bearing pressure of 2,000 pounds per square foot (psf) to 4,000 psf depending on final design column and wall loading, column spacing, settlement tolerances and the final geotechnical investigation.

The Hampshire Companies, LLC
Preliminary Geotechnical Investigation & SWM Area Evaluation
Proposed Mountainside Hospital Redevelopment
One Bay Avenue
Montclair and Glen Ridge, New Jersey
February 5, 2005



Floor Slabs and Pavements: Whitestone preliminarily anticipates that the properly evaluated, prepared and approved existing fill materials, natural site subgrade soils and/or controlled structural imported fill will be suitable for support of the proposed floor slabs and pavements. Subgrade stabilization and protection may be necessary during wet conditions to obtain a stable surface. Subgrade protection may be achieved through the use of separation geotextiles, geogrids, and/or the addition of lime-cement to the subgrade. Limited areas of overexcavation should be anticipated due to portions of the existing fill materials containing objectionable debris.

On-Site Soil Reusability: Whitestone preliminarily anticipates that the majority of the existing fill materials and underlying natural site soils generally will be suitable for reuse as structural fill and/or backfill provided they are free of deleterious debris and moisture contents are controlled within two percent of the optimum and the soils are placed during favorable weather conditions. Based on the conditions disclosed by the subsurface exploration and the results of the laboratory test results, portions of the on-site soils with an appreciable amount of fines may not be suitable for immediate reuse as structural fill and/or backfill due to high moisture content characteristics. Disturbance of these soils should be minimized. The on-site moisture sensitive soils, while stable and often hard when in a dry natural state, will degrade when wetted or disturbed. Whitestone anticipates that the sandy and/or less plastic site soils may be suitable for reuse as structural fill and/or backfill provided moisture contents are controlled within two percent of the optimum only during favorable weather conditions. Due to moisture sensitivity, use of portions of the on-site soils may require mixing with a granular material, extensive moisture conditioning. and/or drying to facilitate their reuse, workability, and compaction in fill areas. These materials will become increasingly difficult to reuse and compact if they become wetted beyond the optimum moisture content. Materials that become exceedingly wet likely will require discing and aerating and extended time to dry during favorable weather. Boulders and cobbles or similarly sized materials greater than three inches in diameter will need to be separated from on-site soils to be placed as structural fill or backfill. Cobbles or boulders between three inches to 12 inches may be crushed or individually placed in structural fill or backfill layers deeper than two feet below proposed foundation and pavement subgraded levels. Care must be taken to individually seat any large particles and to compact soil around large particles with hand operated equipment to minimize risk of void formation. The stripped surface cover materials within the t including asphaltic concrete and topsoil should not be reused as structural fill and/or backfill.

**Excavation Difficulties:** Machine refusal was encountered within the profile pits and auger grinding/split-spoon refusal within the soil borings at depths as shallow as eight fbgs due to the presence of cobbles/boulders. Excavation difficulties will be more prevalent in confined and deep excavations, such as deeper foundations and utilities.

**Demolition Material:** Demolition material and durable material encountered within the existing fill materials, not subject to any environmental restrictions, may be used as fill material provided the material is properly segregated and processed as recommended herein. Concrete masonry materials should be crushed to a well graded blend with a maximum size of three inches in diameter. The asphaltic materials and deleterious debris such as wood, insulation, metal, etc. should not be used as general structural fill material.

**Supplemental Borings:** Supplemental borings should be completed either prior to or once the existing building is demolished to confirm subsurface conditions throughout the site within areas previously inaccessible to conventional truck-mounted drilling equipment at the time of Whitestone's field investigation. Additional borings should be completed in accordance with the New Jersey Building Code requirements.

**Demolition Phase Testing and Inspection:** The owner's geotechnical engineer should perform inspection, testing, and consultation during demolition to confirm all below grade construction is properly removed and any resulting excavations of existing crawl spaces, basements, etc. are properly backfilled. Monitoring and testing should also be performed to verify that the building is properly demolished, any encountered underground structures are properly backfilled, the existing surface cover materials are



properly removed, existing fill materials are overexcavated prior to foundation support and suitable materials are used for controlled fill and that they are properly placed and compacted over suitable subgrade soils. The proofrolling of all subgrades prior initial fill placement to achieve design grades and/or foundation, floor slab and pavement support should be witnessed and documented by the owner's geotechnical engineer as well as foundation and floor slab subgrades prior to concrete placement.

#### 6.0 PRELIMINARY STORMWATER MANAGEMENT EVALUATION

Whitestone's field investigation within the proposed SWM areas consisted of excavating five soil profile pits (identified as SPP-1 through SPP-5), examining soil profiles and performing five laboratory tube permeameter tests. The soils encountered were classified based on the United States Department of Agriculture (USDA) classification system. The location of the profile pits are shown on the *Test Location Plan* included as Figure 1.

Groundwater/Seasonal High Groundwater Levels: Static groundwater or indications of seasonal high groundwater were not encountered within any of the soil profile pits performed within the proposed SWM areas. The methods used in determining the seasonal high groundwater level include evaluating the soil morphology within the soil profile and identifying irregular spots or blotches of different colors or minerals unlike that of the surrounding soil (mottles).

Soil Infiltration Rates: Soil samples were recovered from the varying strata observed within the profile pits performed during Whitestone's subsurface exploration. Representative samples from the anticipated level of infiltration were subjected to tube permeameter analyses as detailed in *New Jersey Stormwater Best Practices Manual*. A summary of the conditions encountered in the test excavations and results of permeability testing are indicated in the table below. Individual tube permeameter test results are provided in Appendix B, soil logs are included in Appendix A.

	SWM PRO	FILE PIT AND PERMEAB	ILITY TEST SUMMAR	RY
Profile Pit and	ESHGW	USDA Classification	Permeab	ility Test
Test #	(fbgs)	@ Permeability Test	Depth (fbgs)	Rate (in/hour)
SPP-1 T-1	NE	Silt Loam	0.5 - 3.75	< 0.2
SPP-1 T-2	NE	Loam	3.75 - 11.5	0.6
SPP-2 T-1	NE	Silt Loam	2.5 - 4.0	< 0.2
SPP-2 T-2	NE	Loam	4.0 - 10.0	0.3
SPP-3 T-1	NE	Silt Loam	1.0 - 2.5	< 0.2
SPP-3 T-2	NE	Loam	2.5 - 11.0	0.4
SPP-4 T-1	NE	Silt Loam	1.5 - 3.0	< 0.2
SPP-4 T-2	NE	Loam	3.0 - 8.0	0.9
SPP-5 T-1	NE	Sandy Loam	0.3 - 8.0	0.5

ESHGW - Estimated Seasonal High Groundwater

NE - Not Encountered



The Hampshire Companies, LLC
Preliminary Geotechnical Investigation & SWM Area Evaluation
Proposed Mountainside Hospital Redevelopment
One Bay Avenue
Montclair and Glen Ridge, New Jersey
February 5, 2015
Page 7

Director, Geotechnical Services

#### 7.0 CLOSING

Whitestone appreciates the opportunity to be of continued service to The Hampshire Companies, LLC. Please note that Whitestone has the capability to perform the additional geotechnical engineering services recommended herein.

Please contact us at (908) 668-7777 with any questions or comments regarding this report.

Sincerely,

WHITESTONE ASSOCIATES, INC.

Mudar Khantamr, E.I.T.

Geotechnical Engineer

MK/pwd L:\Job Folders\2014\1413224GJ\Reports and Submittals\13224 PreGI&SWM.doc

Enclosures

Copy: Donald J. Engels, The Hampshire Companies, LLC Bradford A. Bohler, P.E., Bohler Engineering NJ, LLC

ENVIRONMENTAL & GEOTECHNICAL ENGINEERS & CONSULTANTS

## FIGURE 1 Test Location Plan




FIGURE:

SCALE:

**DATE:** 

PROJ. MGR.: LWK

 $\mathsf{GR}$ 

GJ1413224.000

PROJECT: PROPOSED MOUNTAINSIDE HOSPITAL REDEVELOPMENT

1 BAY AVENUE

TOWNSHIP OF MONTCLAIR & BOROUGH OF GLEN RIDGE, ESSEX COUNTY, NEW JERSEY

BY:

PROJECT #:

01/29/15

# APPENDIX A Records of Subsurface Exploration



#### WHITESTONE RECORD OF ASSOCIATES, INC. SUBSURFACE EXPLORATION **RECORD OF**

Boring No.: B-1 Page 1 of 1

Project:		Propo	sed Mountainside H	Hospita	al Redev	/elopmen	t			WAI Pi	roject No.:	GJ1413224.000	
Location:		One E	Bay Avenue; Montcla	air and	I Glen R	idge; Es	sex County, Ne	w Jerse	еу		Client:	The Hampshire C	Companies, LLC
Surface Ele	evatio	n:	± 254.4 fee	t abov	e msl		Date Started:		1/16/2015	Water Depth	Elevation	Cave-In	Depth   Elevation
Terminatio	n Dep	th:	24.3 fee	t bgs			Date Complete	ed:	1/16/2015	(feet bgs)	(feet msl)	(fe	et bgs)   (feet msl)
Proposed I	Locati	on:	Building				Logged By:	SEP		During: NE	<b>T</b>		
Drill / Test	Metho	d:	HSA / SPT				Contractor:	JG		At Completion: NE	\(\superstandarrangle\)	At Completion:	18.0   236.4 💆
							Equipment:	CME-	55	24 Hours:	· — ▼	24 Hours:	i 🔟
											<u> </u>		·=
	SAI	MPLE	INFORMATION	ı		DEPTH	0.70.47			DECORPTION OF M	ATERIALO		DEMARKO
Depth				Rec.			STRAT	A		DESCRIPTION OF M			REMARKS
(feet)	No	Type	Blows Per 6"	(in.)	N	(feet) 0.0				(Classification	JII)		
						0.4	PAVEMENT		2.5" Asphalt Pave	ment, 2.5" Coarse Gravel			
						0.4	GLACIAL	11111					
						-	DEPOSITS						
		$\backslash \backslash  $					1		Reddish-Brown Si	Ity Sand with Coarse to Fine Su	ibangular and S	Subrounded Gravel	
1 - 3	S-1	ΧI	3 - 7 - 8 - 11	10	15	_	1	Ш	Moist, Medium De		g	,	
		/ N				-	1						
						l –							
3 - 5	S-2	V	6 - 6 - 7 - 9	18	13		]		As Above (SM)				
3-3	0-2	ΛΙ	0 - 0 - 7 - 3	10	15	l .		Ш	AS ABOVE (GIVI)				
		$\triangle$				5.0							
		\											
5 - 7	S-3	ХΙ	16 - 15 - 18 - 27	16	33	_	4		As Above, Dense	(SM)			Lesser Silt Content with
		$/\backslash$											Depth
		$\overline{}$				-							
							4	Ш					
						-	_						
		$\backslash / \mid$				-	-						
8 - 10	S-4	Х	11 - 12 - 17 - 17	16	29	_	1		As Above, Medium	n Dense (SM)			
		$/\ N$				10.0							
						1 -							Some Moderate
													Grinding 10.0 fbgs to 12.0 fbgs
													10.0 lbg3 to 12.0 lbg3
						_							Occasional Brief Auger Grinding on Cobbles/
							_						Boulders
						_	4						12.0 fbgs to 23.0 fbgs
		\ /						Ш					
13 - 15	S-5	Х	19 - 17 - 19 - 32	14	36	_			As Above, Dense	(SM)			
		/  N				15.0							
		-				-							
							1						
						_	1						
						•							
						<u> </u>	<u>잻</u>						
18 - 19.3	S-6	$\bigvee$	29 - 34 - 50/3"	12	84/9"	]	_		As Above, Very D	ense (SM)			
16 - 19.3	5-6	$\Lambda$	29 - 34 - 50/3	12	84/9	_		Ш		,			
						00.0							
						20.0	_						
							4						
						_	-						
						•	1						
						_	1						
						•							
		abla				-							
23 - 24.3	S-7	X	17 - 39 - 50/4"	12	89/10"	•	]		As Above (SM)				
		$\leftarrow$				24.3		14141	Boring Log B-1 Te	erminated at a Depth of 24.3 Fe	et Below Groun	d Surface Due to	
						25.0	_		Split Spoon Samp				



#### WHITESTONE RECORD OF ASSOCIATES, INC. SUBSURFACE EXPLORATION **RECORD OF**

Boring No.: B-2 Page 1 of 1

Project:		Propo	osed Mountainside H	Hospita	al Redev	velopmen	t			WAI Project No.:	GJ1413224.000	
Location:		One E	Bay Avenue; Montcl	air and	d Glen R	Ridge; Ess	sex County, Ne	w Jerse	ey .	Client:	The Hampshire C	Companies, LLC
Surface El	evatio	n:	± 254.0 fee	et abov	e msl		Date Started:	_	1/16/2015	Water Depth   Elevation	Cave-In	Depth   Elevation
Terminatio	n Dep	th:	24.3 fee	et bgs			Date Complete	ed:	1/16/2015	(feet bgs)   (feet msl)	(fe	et bgs)   (feet msl)
Proposed	Locati	on:	Building				Logged By:	SEP		During: <u>NE  </u> <b></b> ▼		(Dry Cave)
Drill / Test	Metho	od:	HSA / SPT				Contractor:	JG		At Completion: NE   ▽	At Completion:	16.0   238.0 💆
							Equipment:	CME-	55	24 Hours:	24 Hours:	<u>\</u>
	SAI	MPL	E INFORMATION	1		DEPTH	STRAT	٠,		DESCRIPTION OF MATERIALS		REMARKS
Depth (foot)	No	Type	Blows Per 6"	Rec.	N	(foot)	OIKAI	^		(Classification)		KEMAKKO
(feet)	NO	Type	Blows Fel 6	(in.)	N	(feet) 0.0				(Glassification)		
						_	PAVEMENT		3" Asphalt Pavem	ent, 4" Coarse Gravel Subbase		
						0.6	FILL	XXX	· .			
						1 -	FILL	$\otimes$				
		$\vee$			_	-		$\otimes$				Apparent Re-Worked
1 - 3	S-1	Λ	3 - 4 - 5 - 11	16	9			$\otimes$	Reddish-Brown Si	lty Sand with Coarse to Fine Gravel, Moist (Fl	LL)	Natural Soils
		/ \				3.0		<b>XXX</b>				
						<u> </u>	GLACIAL	Z				
3 - 5	S-2	V	5 - 5 - 6 - 9	12	11		DEPOSITS	1211	Strong Brown San	ndy Silty Clay, Moist, Very Stiff (CL-ML)		LL = 25, PI = 6
3-3	0-2	Λ	3 - 3 - 0 - 3	12	l ''	_			Ollong Brown Gar	ay dity diay, worst, very diff (de-we)		Qu = 2.0 tsf
		/				5.0						
		\ /				-						
5 - 7	S-3	Υ	13 - 16 - 15 - 15	18	31			Ш		ilty Sand with Coarse to Fine Subangular and	Subrounded Gravel,	
		Λ				-		Ш	Moist, Dense (SM	)		
		igspace				_						
						_						
						-		Ш				
		\ /				-						
8 - 10	S-4	Χ	12 - 23 - 50/3"	4	73/9"	_	_	ШШ	As Above, Very D	ense (SM)		
		$/ \setminus$				10.0	4					
		$\longrightarrow$				10.0		ШШ				Less Silt Content with
						-		Ш				Depth
						_		ШШ				Occassional Brief Auger
						-						Grinding on Cobbles /
						_		Ш				Boulders 10.0 fbgs to 23.0 fbgs
						<u>-</u>						10.0 1290 to 20.0 1290
13 - 13.8	S-5	ackslash	24 - 50/3"	4	50/3"	<u> </u>		Ш	As Above (SM)			
13 - 13.0	3-5	$\triangle$	24 - 50/3	4	50/5	<u> </u>			AS Above (Sivi)			
								Ш				
						15.0						
						_	<u> </u>	Ш				
						<u> 1</u>	<u> </u>					
						-						
						l –	_					
						-	4					
				ļ		<b> </b>	4					
		\ /				<u>-</u>		ШШ				
18 - 20	S-6	Χ	19 - 34 - 41 - 29	12	75	_		Ш	As Above (SM)			
		$/ \setminus$				20.0	4	ШШ				
		-				20.0	_	Ш				
						<u>-</u>	†					
						I —	†					
						-	1					
						I –	1					
							1					
		7				<u> </u>	1					
23 - 24.3	S-7	X	19 - 34 - 50/4"	16	84/10"	·	]		As Above, Trace (	Gravel (SM)		
		$\sim$				24.3		14111	Boring Log B-2 Te	erminated at a Depth of 24.3 Feet Below Groun	nd Surface Due to	
						25.0			Split Spoon Samp		, , 240 10	
				Ī		Ī						



## WHITESTONE RECORD OF ASSOCIATES, INC. SUBSURFACE EXPLORATION

Boring No.: B-3 Page 1 of 1

Project:		Propo	osed Mountainside H	Hospita	al Redev	velopmen	t				WAI Project No.:	GJ1413224.000	
Location:			Bay Avenue; Montcl					w Jerse	<b>Э</b> У		Client:	The Hampshire C	Companies, LLC
Surface El				t abov			Date Started:		1/16/2015	Wate	r Depth   Elevation	Cave-In	Depth   Elevation
Terminatio	n Dep	th:	23.8 fee	t bgs			Date Complet	ed:	1/16/2015	(fe	eet bgs)   (feet msl)	(fe	et bgs)   (feet msl)
Proposed	Locati	on:	Building				Logged By:	SEP		During:	<u>NE  </u> <b> ∆</b>		(Dry Cave)
Drill / Test	Metho	d:	HSA / SPT				Contractor:	JG		At Completion:	<u>NE</u>   ▽	At Completion:	16.0   237.5 <u>a</u>
							Equipment:	CME-	55	24 Hours:	<u></u>	24 Hours:	<u></u>   <u></u> <u>⊠</u>
	SAI	MPLE	E INFORMATION	ı		DEPTH							
Depth				Rec.			STRAT	ΓΑ			N OF MATERIALS		REMARKS
(feet)	No	Type	Blows Per 6"	(in.)	N	(feet) 0.0		1		(Class	sification)		
						0.3	TS FILL	<u>~~</u>	3" Topsoil	Ity Sand with Coarse	to Fine Gravel, No Debri:	Moiet (EILL)	~9' Frost
0 - 2	S-1	V	12 - 7 - 4 - 4	16	11	_	]	<b>XX</b>	Treddish-blown of	ny dana with doarse	to Time Graver, No Debit	s, Wolst (FILL)	-3 11031
0 2	0.	Λ						<b>XX</b>					
		$(\!-\!)$				-	4	$\otimes$					
		$\setminus /$					-	$\times\!\!\times$					
2 - 4	S-2	X	4 - 8 - 15 - 9	8	23	_	1	$\times$	As Above, 10% Fi	ne Coal, Cinders (FIL	.L)		
		$/ \setminus$				4.0		$\bowtie$					
		\					GLACIAL DEPOSITS	Ш					High Moisture Below Fill 4.0 fbgs to 8.0 fbgs
4 - 6	S-3	χ	3 - 3 - 4 - 5	2	7	5.0	- 22. 000		Strong Brown Silt,	Very Moist (ML)			1290 to 0.0 1290
		$/ \setminus$				6.0	1	Ш					
		$\forall$				_		IIII					
6 - 8	S-4	V	10 - 9 - 14 - 19	18	23	_				Ity Sand with Coarse	to Fine Gravel, Very Mois	st, Medium Dense	
		Λ					_	ШШ	(SM)				
8 - 8.1	S-5	$\hookrightarrow$	50/1"	NR	50/1"	- 1	4		No Recovery, Ass	umed as Above (SM)			
0 - 0.1	3-3	$\triangle$	30/1	INIX	30/1		1		110 110001019,7100	amou do / Bovo (Om)			
						_	]						
						10.0							
							4						
						-	-	Ш					Regular Auger Grinding
						•	1						~11.0 fbgs to 23.0 fbgs
							]	Ш					
						- 1	_						
		$\setminus /$					4	Ш					
13 - 15	S-6	Χ	9 - 12 - 16 - 27	18	28	-	┪	Ш	Reddish-Brown Si	Ity Sand with Coarse	to Fine Gravel, Moist, Me	edium Dense (SM)	
		$/\setminus$				15.0	Ī	ШШ					
						Ι,	]	Ш					
						<u>-</u>	<u></u> 결						
							1						
						-	1						
							]						
18 - 19.2	S-7	$\bigvee$	17 - 32 - 50/2"	10	82/8"		4		As Above, Very De	ense (SM)			
.5 15.2	<i>3 1</i>	$\triangle$	32 30/2		JZ, 0	] -	1						
						20.0	1						
													Lesser Silt Content with
						_	4						Depth
							4						
						-	1						
						-	1						
23 - 23.8	S-8	X	21 - 50/3"	8	50/3"	<u> </u>	]		As Above (SM)				
						23.8	<del>                                     </del>	21.114			of 23.8 Feet Below Groun	d Surface Due to	
						25.0	-		Split Spoon Samp	ler Refusal			
							1						



## RECORD OF SUBSURFACE EXPLORATION

Page 1 of 1

	-										
Project:		Propo	osed Mountainside H	Hospita	al Redev	/elopmen	t			WAI Project No.: GJ1413224.000	
Location:		-	Bay Avenue; Montcl	-		•		w Jers	ey	Client: The Hampshire Comp	panies, LLC
Surface El	evatio				e msl		Date Started:		1/16/2015		pth   Elevation
Terminatio	n Dep	th:		t bgs			Date Complete	ed:	1/16/2015		gs)   (feet msl)
Proposed			Building				Logged By:	SEP			(Dry Cave)
Drill / Test			HSA / SPT				Contractor:	JG		÷	0.0   235.0
,							Equipment:	CME	-55	24 Hours: — — — — 24 Hours:	<u>\</u>
	SA	MPLE	E INFORMATION	ı		DEPTH					
Depth				Rec.			STRAT	Α		DESCRIPTION OF MATERIALS	REMARKS
(feet)	No	Type	Blows Per 6"	(in.)	N	(feet)				(Classification)	
						0.0	TS	<u> </u>	5" Topsoil		
		$\backslash$				0.4	GLACIAL	1111		Silty Sand with Coarse to Fine Subangular/Subrounded Gravel,	
0 - 2	S-1	ΙXΙ	1 - 3 - 7 - 12	16	10	_	DEPOSITS		Moist, Medium De	ense (SM)	
		$/ \setminus$					1				
		$(\ )$				-	1	Ш			
		V				-					
2 - 4	S-2	ΙĂΙ	12 - 11 - 12 - 19	8	23	_	1		As Above (SM)		
		$V\setminus$					1	Ш			
						_	]				
4 - 6	S-3	IV	11 - 11 - 14 - 14	14	25	5.0			As Above (SM)		
4-0	0-3	$ \Lambda $	11 - 11 - 14 - 14		2.5				AS ABOVE (OW)		
		$\langle \ \ \ \rangle$				_	_	Ш			
								Ш			
						_					
							4				
		$\overline{}$				-	4			Pog	gular Auger Grinding
8 - 9.3	S-4	$ \nabla $	16 - 27 - 50/4"	8	77/10"		4		As Above, Very D	9.0	fbgs to 13.5 fbgs
0 - 3.5	0 4	$ \Lambda $	10 - 21 - 30/4	0	77710	_	1		As Above, very b	verise (GW)	
						10.0	<b>Z</b>				
							ī				
						-	1	Ш			
						_	1				
								Ш			
						_		Ш	I		
13 - 13.5	S-5	$\times$	29-50/0"	4	50/0"	13.5		1111	As Above (SM)		oon Bouncing
						_	-			erminated at a Depth of 13.5 Feet Below Ground Surface Due to  Auger Refusal on Presumed Boulder	
						15.0	-				
						13.0	1				
							1		I		
						_	1		I		
						•	1				
						_	1				
						•	]		I		
						_					
							_				
						20.0					
							4				
						_	-				
							-		I		
						_	-				
							1				
						_	1		I		
						•	1		I		
						-	1				
				l	I	05.0	┪				



#### **RECORD OF** WHITESTONE RECORD OF ASSOCIATES, INC. SUBSURFACE EXPLORATION

Boring No.: B-5 Page 1 of 1

Project:		Propo	osed Mountainside I	Joenite	al Raday	/elonment					WAID	oject No.:	GJ1413224.000	
								u loro	N/		WALL		The Hampshire (	Componies IIC
Location:			Bay Avenue; Montol							· · · ·		Client:	T	
Surface El				et abov	e msi		Date Started:	•	1/16/2015			Elevation		Depth   Elevation
Terminatio	-		5.0fee	et bgs			Date Complete		1/16/2015			(feet msl)	(fe	et bgs)   (feet msl)
Proposed	Locati	on:	Pavement				.ogged By:	SEP		During:	NE	<u></u> Ā		
Drill / Test	Metho	od:	HSA / SPT				Contractor:	JG		At Completion:	NE	<u></u> ▽	At Completion:	<u>NE  </u> <u>⊠</u>
						E	quipment:	CME-	55	24 Hours:		<b>y</b>	24 Hours:	<u></u>   <u></u> <u>\</u>
														<u> </u>
	SAI	MPLE	E INFORMATION	ı		DEPTH	STRAT			DESCRIPTIO	N OE M	ATEDIALS		REMARKS
Depth		_	D. D. O.	Rec.		"	SIRAI	^			sification			KEWIAKKS
(feet)	No	Type	Blows Per 6"	(in.)	N	(feet) 0.0				(Clas	Silicatio	ווע		
						0.0	PAVEMENT		4" Asphalt Payem	ent, 3" Coarse Grave	al Subbase			1
						0.6			4 / Tophait I avoin	oni, o oddioc olave	or Gubbase			Very Moist Beneath Subbase
		$\overline{}$				0.0	GLACIAL DEPOSITS							Derieatii Subbase
		$\setminus /$				-	DEI OONO							
1 - 3	S-1	Х	2 - 2 - 3 - 5	14	5	_			Strong Brown Silt	with Sand, Very Mois	st to Moist,	Medium Stiff to	Very Stiff (ML)	Qu = 0.5 tsf to 2.0 tsf
		/ \				3.0								
		$\mapsto$				<u> </u>		14134						
		$\setminus \setminus$				_								
3 - 5	S-2	Х	4 - 8 - 7 - 8	16	15	_			Reddish-Brown Si	Ity Sand with Coarse	to Fine Gr	avel, Moist, Me	edium Dense (SM)	
		$/ \setminus$				5.0			I					
									Boring Log B-5 Te	erminated at a Depth	of 5.0 Feet	Below Ground	Surface	
						-								
						_								
						<u> </u>								
						_								
						10.0								
						l _								
						<u> </u>								
						l <u> </u>								
						_								
						_								
						15.0								
						<u> </u>								
						l —								
						-			I					
						l <u> </u>			I					
						-			I					
						<u> </u>			I					
						-								
						l —			I					
						20.0								
						20.0								
						-								
						I —								
						-								
						<u> </u>			I					
						-			I					
						l —			I					
						-			I					
						l —			I					
						25.0			I					
						_								



## WHITESTONE RECORD OF ASSOCIATES, INC. SUBSURFACE EXPLORATION

Boring No.: B-6 Page 1 of 1

Project:		Propo	osed Mountainside H	Hospita	al Redev	velopmen	t			WAI Project No	: GJ1413224.000	
Location:		One E	Bay Avenue; Montcl	air and	d Glen F	Ridge; Ess	sex County, Ne	w Jerse	y ·	Clien	: The Hampshire (	Companies, LLC
Surface El	evatio	n:	± 248.5 fee	et abov	e msl		Date Started:		1/16/2015	Water Depth   Elevation	n Cave-Ir	Depth   Elevation
Terminatio	n Dep	th:	6.0 fee	et bgs			Date Complete	ed:	1/16/2015	(feet bgs)   (feet ms	I) (fe	et bgs)   (feet msl)
Proposed	Locati	on:	Pavement				Logged By:	SEP		During: NE	<u> </u>	
Drill / Test	Metho	d:	HSA / SPT				Contractor:	JG			At Completion:	NE   🖼
							Equipment:	CME-5	55		24 Hours:	i 💆
				_							<sup>f</sup>	·=
	SAI	MPLE	E INFORMATION	1		DEPTH	l					
Depth				Rec.			STRAT	Α		DESCRIPTION OF MATERIA	LS	REMARKS
(feet)	No	Type	Blows Per 6"	(in.)	N	(feet)				(Classification)		
						0.0	TS	<u> </u>	4" Topsoil			
		\ /				0.3	FILL	588	Gray Silty Sand w	ith Coarse to Fine Gravel and Debris, Mois	t (FILL)	Debris: Fine Coal and
0 - 2	S-1	χ	6 - 5 - 5 - 5	20	10	4.5	-	<b>**</b>				Brick
		$/\backslash$				1.5	GLACIAL	XXX	Strong Brown San	dy Silt, Moist, Medium Stiff (ML)		
		$(\!$		$\vdash$			DEPOSITS		Ottorig Brown Gar	ay ont, worst, wediam our (we)		
		\/				3.0	-		As Above (ML)			
2 - 4	S-2	Χ	6 - 6 - 7 - 9	18	13	0.0	1	11111		Ity Sand with Gravel, Moist, Medium Dens	e (SM)	
		$/ \setminus$				-	1				(4.1.)	
		$(\!$				_	1					
		\/				5.0	1					
4 - 6	S-3	Х	10 - 11 - 11 - 16	18	22		1		As Above (SM)			
		/\				-	1					
								1.71.41	Boring Log B-6 Te	erminated at a Depth of 6.0 Feet Below Gro	und Surface	
						-	1					
						-	1					
						_	1					
						-	1					
							1					
						10.0	1					
							1					
							1					
							1					
						_						
							J					
						15.0						
						_						
					1	] -	4					
					1	_	4					
					1	] .	4					
					1	<u> </u>	4					
						-	4					
						_	-					
						20.0	4					
					1	20.0	-					
					1	-	-					
					1	-	-					
					1	-	-					
					1	I –	-					
					1	-	-					
					1	-	-					
					1	-	-					
					1	l –	4					
					1	25.0	-					
					1		-					
			1	1 !	ı							i l



## RECORD OF SUBSURFACE EXPLORATION

Soil Profile Pit No.: SPP-1

Page 1 of 1

Project: Propose	d Mountainside Hospital Redeve	opment			WAI P	roject No.:		GJ1413224.000
Location: One Bay	Avenue; Montclair and Glen Rid	ge; Essex County, Ne	ew Jersey			Client:		The Hampshire Companies, LLC
Surface Elevation:	± 248.5 feet above msl	Date Started:	1/16/2015	Water	Depth	Elevation		Estimated Seasonal High
Termination Depth:	11.5 feet bgs	Date Completed:	1/16/2015	(fee	et bgs)	(feet msl)		Groundwater Depth   Elevation
Proposed Location:	SWM	Logged By:	SEP	During:	NE		$ar{m{\Lambda}}$	(feet bgs)   (feet msl)
Excavating Method:	Test Pit Excavation	Contractor:	Carroccia	At Completion:	NE		$\nabla$	At Completion: NE
Test Method:	Visual Observation	Rig Type:	DEERE 310 SG	24 Hours:			lacksquare	
				-				

st Method:	etilou.	Visual Obs	servation		Rig Type:	DEERE 310 SG 24 Hours:	NE
SAMPLE Depth (feet)	INFORM Number	ATION Type		PTH	HORIZON	DESCRIPTION OF MATERIALS (Classification)	REMARKS
eptii (leet)	Number	Туре	0.0	0 - 0.5	TOPSOIL	6" Topsoil	
			1.0	0.5 - 3.8	SILT LOAM	Strong Brown (7.5YR 5/6) SILT LOAM; 10% Gravel; Moderate, Medium Subangular Blocky Structure; Moist; Friable; No Mottling: Many Medium to Fine Roots @ 0.5 fbgs to 3.5 fbgs, Few Fine Roots @ 2.5 fbgs to 3.75 fbgs; Clear Wavy Boundary	
).5 - 3.75	S-1 T-1A/B	BAG TUBES	2.0				
			3.0				
			4.0	3.8 - 11.5	LOAM	Dark Reddish-Brown (2.5YR 3/4) LOAM; 15% Gravel, 10% Cobbles; Moderate, Medium Subangular Blocky to Crumb Structure; Moist; Friable; Few Fine Roots; No Mottling	
			5.0				
			6.0 				Cobble/Boulder Conter Increasing with Depth 2' Maximum Diameter
.75 - 11.5	S-2 T-2A/B	BAG TUBES	8.0				
			9.0				
			10.0				
			11.0				
			12.0			Soil Profile Pit SPP-1 Terminated at a Depth of 11.5 Feet Below Ground Surface Due to Practical Extents (Due to Site Constraints and Boulders)	
			13.0				
			14.0				
			15.0				



#### **RECORD OF** VHITESTONE SSOCIATES, INC. SUBSURFACE EXPLORATION

Soil Profile Pit No.: SPP-2 Page 1 of 1

Project: Proposed Mountainside Hospital Redev	elopment			WAI P	roject No.:		GJ1413224.000	
Location: One Bay Avenue; Montclair and Glen R	dge; Essex County, N	ew Jersey			Client:		The Hampshire Companies, LLC	
Surface Elevation: ± 252.0 feet above msl	Date Started:	1/16/2015	Water	Depth	Elevation		Estimated Seasonal High	
Termination Depth: 10.0 feet bgs	Date Completed:	1/16/2015	(fee	et bgs)	(feet msl)		Groundwater Depth   Elevation	
Proposed Location: SWM	Logged By:	SEP	During:	NE		$\bar{\boldsymbol{L}}$	(feet bgs)   (feet msl)	
Excavating Method: Test Pit Excavation	Contractor:	Carroccia	At Completion:	NE		$\nabla$	At Completion: NE	
Test Method: Visual Observation	Rig Type:	DEERE 310 SG	24 Hours:			lacksquare		
·			_			•		

Excavating M	ethod:	Test Pit Ex	xcavation	1	Contractor:	Carroccia At Completion: NE     At Completion:	NE
Test Method:		Visual Obs	servation	ı	Rig Type:		
SAMPLE	INFORM	MATION	DE	PTH	HORIZON	DESCRIPTION OF MATERIALS	REMARKS
Depth (feet)	Number	Туре	feet	inches	HORIZON	(Classification)	REMARKO
			0.0				
				0 - 0.8	TOPSOIL	9" Topsoil	
			_	-			
			1.0	0.8 - 2.5	FILL	Reddish-Brown Silty Sand; 15% Gravel, 10% Cobbles; Structureless; Most; Many Fine to Medium	Probable Re-Worked
						Roots; Clear Wavy Boundary	On-Site Soils 0.75 fbgs to 2.5 fbgs
			2.0	1			
			2.0	1			
			_	0.5.4	01171.0444	20	
			3.0	2.5 - 4	SILT LOAM	Strong Brown (7.5YR 5/6) SILT LOAM; 5% Gravel; Moderate, Medium Subangular Blocky to Crumb Structure; Moist; Friable; Few Fine Roots; No Mottling; Clear Wavy Boundary	
2.5 - 4	S-1 T-1A/B	BAG TUBES					
	1-17/15	TOBES	_	1			
			4.0	4 - 10	LOAM	Dark Reddish-Brown (2.5YR 3/4) LOAM; 20% Gravel, 15% Cobbles, 5% Boulders; Moderate,	1
			_	7-10	LOAW	Medium Subangular Blocky Structure; Moist; Friable; Few Fine Roots; No Mottling	
			5.0				
			_	1			
			_	1			Cobble/Boulder Content
			6.0				Increasing with Depth 3' Maximum Diameter
							3 Maximum Diameter
	0.0	DAG	7.0	1			
4 - 10	S-2 T-2A/B	BAG TUBES		1			
			-	4			
			8.0				
			_	1			
			9.0	1			
			_				
			10.0				
						Soil Profile Pit SPP-2 Terminated at a Depth of 10.0 Feet Below Ground Surface Due to Practical Refusal and Site Restraints	
			-	1		Tronsoar and Otto reogramio	
			11.0	-			
			_				
			12.0				
			_	1			
			_	-			
			13.0				
			14.0	]			
				1			
			_	-			
			15.0				
		<u> </u>		<u></u>			



#### **RECORD OF** WHITESTONE RECORD OF ASSOCIATES, INC. SUBSURFACE EXPLORATION

Soil Profile Pit No.: SPP-3 Page 1 of 1

Project: Proposed N	Mountainside Hospital Redevel	opment			WAI P	roject No.:		GJ1413224.000		
Location: One Bay A	venue; Montclair and Glen Ride	ge; Essex County, Ne	ew Jersey			Client:		The Hampshire Companies, LLC		
Surface Elevation: $\pm$	248.0 feet above msl	Date Started:	1/16/2015	Water	Depth	Elevation		Estimated	l Season	al High
Termination Depth:	11.0 feet bgs	Date Completed:	1/16/2015	(fee	et bgs)	(feet msl)		Groundwate	Depth	Elevation
Proposed Location:	SWM	Logged By:	SEP	During:	NE		$\bar{\boldsymbol{L}}$	(fe	et bgs)	(feet msl)
Excavating Method:	Test Pit Excavation	Contractor:	Carroccia	At Completion:	NE		$\nabla$	At Completion:	NE	
Test Method:	/isual Observation	Rig Type:	DEERE 310 SG	24 Hours:			lacksquare			
_				<u> </u>						

Excavating iv		Visual Obs			Rig Type:	DEERE 310 SG 24 Hours:   Y At Completion:	<u>NE  </u>
SAMPLE				PTH	<b>3</b> 71		
Depth (feet)	Number	Type	feet	inches	HORIZON	DESCRIPTION OF MATERIALS (Classification)	REMARKS
Deptii (leet)	Number	Туре	0.0	inches		( )	
				0 - 0.3	TOPSOIL	3" Topsoil	
			_	0.3 - 1	FILL	Brown and Gray Silty Sand with 20% Coarse to Fine Angular Gravel	
			1.0	1 - 2.5	SILT LOAM	Strong Brown (7.5YR 5/6) SILT LOAM; 10% Gravel; Moderate, Medium Subangular Blocky Structure;	
1 - 2.5	S-1	BAG	_			Moist; Friable; Few Fine Roots; No Mottling; Clear Wavy Boundary	
1 - 2.5	T-1A/B	TUBES	2.0				
			-	2.5 - 11	LOAM	Dark Reddish-Brown (2.5YR 3/4) LOAM; 20% Gravel, 10% Cobbles, 5% Boulders; Moderate,	
			3.0			Medium Subangular Blocky to Crumb Structure; Moist; Friable No Roots; No Mottling	
			_				
			4.0				Cobbles/Boulders Content
			_				Increasing with Depth
			5.0				
			_				
			6.0				
0.5.44	S-2	BAG	_				
2.5 - 11	T-2A/B	TUBES	7.0				
			_				
			8.0				
			_				
			9.0				
			_				
			10.0				
			_				
			11.0			Soil Profile Pit SPP-3 Terminated at a Depth of 11.0 Feet Below Ground Surface Due to Practical	
			-			Refusal on Cobbles/Boulders	
			12.0				
			-				
			13.0				
			-				
			14.0				
			-				
			15.0				



## RECORD OF SUBSURFACE EXPLORATION

Soil Profile Pit No.: SPP-4

Page 1 of 1

Project: Propose	ed Mountainside Ho	lospital Redevelo	pment			WAI P	roject No.:		GJ1413224.000		
Location: One Ba	y Avenue; Montclai	air and Glen Ridg	e; Essex County, Ne	ew Jersey			Client:		The Hampshire Con	npanies, LL	С
Surface Elevation:	± 245.5 feet a	above msl	Date Started:	1/16/2015	Water	Depth	Elevation		Estimated S	Seasonal H	ligh
Termination Depth:	13.0 feet b	bgs	Date Completed:	1/16/2015	(fee	et bgs)	(feet msl)		Groundwater I	Depth   Ele	evation
Proposed Location:	SWM	_	Logged By:	SEP	During:	NE		$ar{m{\Lambda}}$	(feet	t bgs)   (fe	eet msl)
Excavating Method:	Test Pit Excavat	ation	Contractor:	Carroccia	At Completion:	NE		$\nabla$	At Completion:	NE	
Test Method:	Visual Observat	tion	Rig Type:	DEERE 310 SG	24 Hours:	<u></u>		₹			
					_						

est Method:		Visual Obs	servation		Rig Type:	DEERE 310 SG	
SAMPLE Depth (feet)	T			PTH	HORIZON	DESCRIPTION OF MATERIALS (Classification)	REMARKS
Depth (feet)	Number	Туре	feet 0.0	inches		(Classification)	
				0 - 0.5	TOPSOIL	6" Topsoil	
			_	0.5 - 1.5	FILL	Gray Silt and Sand with Gravel and Debris	Metal Pipe and Wire
			1.0				Encountered (Apparentl Abandoned)
			_	1.5 - 3	SILT LOAM	Strong Brown (7.5YR 5/6) SILT LOAM; 10% Gravel; Moderate, Medium Subangular Blocky Structure;	
1.5 - 3	S-1	BAG	2.0			Moist; Friable; Few Fine Roots; No Mottling; Clear Wavy Boundary	
	T-1A/B	TUBES	_				
			3.0	3 - 8	LOAM	Dark Reddish-Brown (2.5YR 3/4) LOAM; 20% Gravel, 10% Cobbles, 5% Boulders; Moderate,	
						Medium Subangular Blocky Structure; Moist; Friable; Few Fine Roots; No Mottling; Clear Wavy Boundary	
			4.0				
			_				
			5.0				
3 - 8	S-2 T-2A/B/C	BAG TUBES	_				
			6.0				
			_				
			7.0				
			_				
			8.0	8 - 13	SANDY LOAM	Reddish-Brown (2.5YR 4/4) SANDY LOAM; 15% Gravel, 5% Cobbles, 5% Boulders; Moderate,	-
			_			Medium Crumb Structure; Moist; Friable; No Roots; No Mottling	
			9.0				
			_	,			
			10.0				
8 - 13	S-3	BAG	_				
			11.0				
			_				
			12.0				
			_				
			13.0				
			_			Soil Profile Pit SPP-4 Terminated at a Depth of 13.0 Feet Below Ground Surface	
			14.0				
			_				
			15.0				



#### **RECORD OF** WHITESTONE RECORD OF SUBSURFACE EXPLORATION

Soil Profile Pit No.: SPP-5 Page 1 of 1

Project: Proposed Mountainside Hospital Red	velopment			WAI P	roject No.:		GJ1413224.000	
Location: One Bay Avenue; Montclair and Glen	Ridge; Essex County, N	lew Jersey			Client:		The Hampshire Companies, LLC	
<b>Surface Elevation:</b> $\pm$ <u>243.0</u> feet above msl	Date Started:	1/16/2015	Water	Depth	Elevation		Estimated Seasonal High	
Termination Depth: 8.0 feet bgs	Date Completed:	1/16/2015	(fee	et bgs)	(feet msl)		Groundwater Depth   Elevation	
Proposed Location: SWM	Logged By:	SEP	During:	NE		$\bar{\boldsymbol{L}}$	(feet bgs)   (feet msl)	
Excavating Method: Test Pit Excavation	Contractor:	Carroccia	At Completion:	NE		$\nabla$	At Completion: NE	
Test Method: Visual Observation	Rig Type:	DEERE 310 SG	24 Hours:			${\bf \bar A}$		
·								

Test Method:		Visual Obs			Rig Type:	DEERE 310 SG	24 Hours:		At Completion.	INL
SAMPLE	T			PTH	HORIZON	D	ESCRIPTION OF MATE (Classification)	ERIALS		REMARKS
Depth (feet)	Number	Туре	0.0	0 - 0.3 0.3 - 8	TOPSOIL SANDY LOAM		NDY LOAM; 15% Gravel, 10% ructure; Moist; Friable; Few Fine			
			2.0							
	S-1	BAG	3.0							
0.3 - 8	T-1A/B/C	TUBES	5.0							
			7.0							
			8.0			Soil Profile Pit SPP-5 Terminat Constraints and Presence of B	ted at a Depth of 8.0 Feet Below oulders	r Ground Surface D	ue to Site	
			9.0							
			11.0							
			12.0							
			14.0							
			15.0							




## RECORD OF SUBSURFACE EXPLORATION

Soil Profile Pit No.: SPP-6

	11330	CIAIL	o, II VC		306	SORFACE E	IAPLORAI	ION				Page 1 of	1	
Project:	Proposed	Mountains	ide Hosp	ital Redeve	elopment			WAI P	roject No.:		GJ1413224.000			
Location:	One Bay	Avenue; Mo	ontclair a	nd Glen Ri	dge; Essex Count	y, New Jersey			Client:	The Hampshire Companies, LLC				
Surface Elevation: ± 243.5 feet above msl		Date Started:	1/16/2015	Water	Depth	Elevation		Estimated	d Seasonal High					
Termination I	Depth:	2.0	feet bgs		Date Complete	ed: 1/16/2015	(fee	et bgs)	(feet msl)	1	Groundwate	r Depth   Elevation	n	
Proposed Lo	cation:	SWM	_		Logged By:	SEP	During:	NE		$\bar{\boldsymbol{L}}$	(fe	et bgs)   (feet msl	I)	
Excavating Method: Test Pit Excavation		Contractor:	Carroccia	At Completion:	NE		$\nabla$	At Completion:	NE					
Test Method:		Visual Obs	servation		Rig Type:	DEERE 310 SG	24 Hours:			▼			_	
SAMPLE	INFORM	IATION	DE	PTH	HORIZON	DESCRIPTION OF MATERIALS						REMARKS		
Depth (feet)	Number	Туре	feet	inches	HORIZON		(Classifi	cation)				I TEMPATO		
			0.0											
			0.0		TOPSOIL T	ГорѕоіІ						1		
				<del> </del>								i		

## **APPENDIX B Laboratory Test Results**



SIEVE	PERCENT	SPEC.*	PASS?
SIZE	FINER	PERCENT	(X=NO)
1 in. 3/4 in. 3/8 in. #4 #10 #20 #40 #60 #140 #200	100.0 91.9 81.0 75.6 72.2 68.5 64.3 57.5 38.4 32.9		

	Soil Description								
Silty sand with g	Silty sand with gravel								
<b>-</b>	Atterberg Limits								
PL= NP	LL=	PI= NP							
D <sub>85</sub> = 13.3 D <sub>30</sub> = C <sub>u</sub> =	<u>Coefficients</u> D <sub>60</sub> = 0.291 D <sub>15</sub> = C <sub>c</sub> =	D <sub>50</sub> = 0.177 D <sub>10</sub> =							
USCS= SM	Classification AASHT	O=							
$W_n = 10.1 \%$	<u>Remarks</u>								

\* (no specification provided)

Sample No.: S-3 Location: Source of Sample: B-1

**Elev./Depth:** 5.0' - 7.0'

**Date:** 01/28/2015


WHITESTONE ASSOCIATES, INC.

**Client:** The Hampshire Companies, LLC

**Project:** Proposed Mountainside Hospital Redevelopment

One Bay Ave; Montclair and Glen Ridge, Essex County, NJ

Project No: GJ1413224.000 Plate



SIEVE	PERCENT	SPEC.*	PASS?
SIZE	FINER	PERCENT	(X=NO)
3/4 in. 3/8 in. #4 #10 #20 #40 #60 #140 #200	100.0 95.7 89.9 85.6 83.3 80.4 74.6 60.2 57.6		

Sandy silty clay	Soil Description	
PL= 19	Atterberg Limits	PI= 6
D <sub>85</sub> = 1.64 D <sub>30</sub> = C <sub>u</sub> =	$\begin{array}{c} \underline{\text{Coefficients}} \\ \overline{\text{D}_{60}} = 0.104 \\ \overline{\text{D}_{15}} = \\ \overline{\text{C}_{\text{C}}} = \end{array}$	D <sub>50</sub> = D <sub>10</sub> =
USCS= CL-M	Classification L AASHT	·O=
$W_n = 15.0 \%$	<u>Remarks</u>	

\* (no specification provided)

Sample No.: S-2 Location: **Source of Sample:** B-2

**Elev./Depth:** 3.0' - 5.0'

**Date:** 01/28/2015


WHITESTONE ASSOCIATES, INC.

**Client:** The Hampshire Companies, LLC

**Project:** Proposed Mountainside Hospital Redevelopment

One Bay Ave; Montclair and Glen Ridge, Essex County, NJ

Project No: GJ1413224.000 Plate



SIEVE	PERCENT	SPEC.*	PASS?
SIZE	FINER	PERCENT	(X=NO)
1.5 in. 1 in. 3/4 in. 3/8 in. #4 #10 #20 #40 #60 #140 #200	100.0 86.4 86.4 80.1 75.6 71.7 69.3 65.6 54.1 27.2 21.4		

Silty sand with g	Soil Description	1
PL= NP	Atterberg Limits	S PI= NP
D <sub>85</sub> = 16.5 D <sub>30</sub> = 0.119 C <sub>u</sub> =	$\begin{array}{c} \underline{\text{Coefficients}} \\ \overline{\text{D}_{60}} = 0.312 \\ \overline{\text{D}_{15}} = \\ \overline{\text{C}_{\text{C}}} = \end{array}$	D <sub>50</sub> = 0.219 D <sub>10</sub> =
USCS= SM	Classification AASH	ГО=
$W_n = 6.3 \%$	<u>Remarks</u>	

\* (no specification provided)

Sample No.: S-6 Location: Source of Sample: B-2

**Elev./Depth:** 18.0' - 20.0'

**Date:** 01/28/2015

WHITESTONE ASSOCIATES, INC.

**Client:** The Hampshire Companies, LLC

**Project:** Proposed Mountainside Hospital Redevelopment

One Bay Ave; Montclair and Glen Ridge, Essex County, NJ

Project No: GJ1413224.000 Plate

Other - Specify \_\_\_

Project: Proposed Mountainside Hospital Redevelopment
Client: The Hampshire Companies, LLC T-1 \_\_\_\_ Depth: Sample ID: Profile Pit No.: SPP-1 Sample No.: 0.5'-3.75' Lab Tech: DO BLOCK LOT COUNTY/MUNICIPALITY Essex 1/16/2015 1 Replicate (letter) \_\_\_\_ A \_\_\_ Date Collected 1. Test Number X Test in Native Soil Fill 2. Material Tested: Disturbed X Undisturbed 3. Type of Sample: 4. Sample Dimensions: Inside Radius of Sample Tube, R, in cm Length of Sample, L, in inches 5. Bulk Density Determination (Disturbed Samples Only): N/A Wt. of Tube Containing Sample \_ 6. Sample Weight (Wt. Tube Containing Sample-Wt. of Empty Tube), grams 0.00 Wt. of Empty Tube 7. Sample Volume (L x 2.54 cm./inch x 3.14R2), cc. 68.74 0 > 1.2 8. Bulk Density (Sample Wt./Sample Volume), grams/cc. Yes, Indicate Internal Radius, cm. N/A \_\_\_\_X\_\_\_No 9. Standpipe Used: 10. Height of Water Level Above Rim of Test Basin, in inches: At the Beginning of Each Test Interval, H1 At the End of Each Test Interval, H2 4.75 4.63 11. Rate of Water Level Drop (Add additional lines if needed): Time End of Test Length of Test Time, Start of Test Interval, T, Minutes Interval T2 Interval, T1 210.00 K,  $(in/hr) = 60 \text{ min/hr} \times r2/R2 \times L(in)/T(min) \times ln (H1/H2)$  T= 210.00 12. Calculation of Permeability: K (in/hr) = 0.02 Classification: 13. Defects in the Sample (Check appropriate items): \_\_ None Large Gravel \_\_\_\_ \_\_\_\_Large Roots \_\_Soil/Tube Contact \_\_\_\_ \_\_\_\_\_Dry Soil \_\_\_\_\_\_Smearing \_\_\_\_\_\_Compaction

Project: Proposed Mountainside Hospital Redevelopment SPP-1 Depth: Client: The Hampshire Companies, LLC Profile Pit No.: Sample No.: 0.5'-3.75' Sample ID: Lab Tech: DO COUNTY/MUNICIPALITY Essex BLOCK LOT B Date Collected 1/16/2015 1 Replicate (letter) 1. Test Number 2. Material Tested: Fill X Test in Native Soil 3. Type of Sample: X Undisturbed \_\_ Disturbed Inside Radius of Sample Tube, R, in cm 4. Sample Dimensions: 3.00 Length of Sample, L, in inches 5. Bulk Density Determination (Disturbed Samples Only): N/A Wt. of Tube Containing Sample \_\_\_ 6. Sample Weight (Wt. Tube Containing Sample-Wt. of Empty Tube), grams 0.00 Wt. of Empty Tube 86.83 7. Sample Volume (L x 2.54 cm./inch x 3.14R2), cc. 8. Bulk Density (Sample Wt./Sample Volume), grams/cc. 0 > 1.2 Yes, Indicate Internal Radius, cm. N/A 9. Standpipe Used: \_\_\_\_X\_\_\_No 10. Height of Water Level Above Rim of Test Basin, in inches: At the Beginning of Each Test Interval, H1 At the End of Each Test Interval, H2 4.75 11. Rate of Water Level Drop (Add additional lines if needed): Time, Start of Test Time End of Test Length of Test Interval T2 Interval, T, Minutes Interval, T1 360.00 12. Calculation of Permeability: K,  $(in/hr) = 60 \text{ min/hr} \times r2/R2 \times L(in)/T(min) \times ln (H1/H2)$  T= 360.00 K (in/hr) = 0.00 Classification: K0 13. Defects in the Sample (Check appropriate items): \_\_\_ None Soil/Tube Contact \_\_\_\_\_Large Gravel \_\_\_\_\_ Large Roots \_\_\_\_Smearing \_\_\_\_\_Compaction \_\_\_ Dry Soil \_\_\_\_ \_\_ Other - Specify \_\_\_

\_\_\_\_ Other - Specify \_\_\_

Project: Proposed Mountainside Hospital Redevelopment
Client: The Hampshire Companies, LLC T-2 Depth: 3.75'-11.5' Sample ID: Profile Pit No.: SPP-1 Sample No.: Lab Tech: DO BLOCK COUNTY/MUNICIPALITY Essex \_\_\_\_A Date Collected 1 Replicate (letter) 1/16/2015 1. Test Number \_\_\_\_X Test in Native Soil 2. Material Tested: Fill X Undisturbed Disturbed 3. Type of Sample: Inside Radius of Sample Tube, R, in cm 4. Sample Dimensions: Length of Sample, L, in inches 5. Bulk Density Determination (Disturbed Samples Only): N/A Wt. of Tube Containing Sample 0.00 6. Sample Weight (Wt. Tube Containing Sample-Wt. of Empty Tube), grams Wt. of Empty Tube 7. Sample Volume (L x 2.54 cm./inch x 3.14R2), cc. 65.12 0 > 1.2 8. Bulk Density (Sample Wt./Sample Volume), grams/cc. Yes, Indicate Internal Radius, cm. N/A X No 9. Standpipe Used: 10. Height of Water Level Above Rim of Test Basin, in inches: At the Beginning of Each Test Interval, H1 4.63 At the End of Each Test Interval, H2 3.63 11. Rate of Water Level Drop (Add additional lines if needed): Length of Test Time, Start of Test Time End of Test Interval, T, Minutes Interval, T1 Interval T2 53.50 55.25 55.50 K,  $(in/hr) = 60 \text{ min/hr} \times r2/R2 \times L(in)/T(min) \times ln (H1/H2)$  T= 54.75 12. Calculation of Permeability: Classification: K2 K (in/hr) = 0.60 13. Defects in the Sample (Check appropriate items): None \_\_ Soil/Tube Contact \_\_\_\_ Large Roots \_\_\_Large Gravel \_\_\_\_ Dry Soil \_\_\_\_\_\_ Smearing \_\_\_\_\_ Compaction

		11	ibe reillie	ameter	est Date	•			Project:	Proposed Mountainside Hospital Redevelopment
Sample ID:	Profile l	Pit No.:	SPP-1	Sampl	e No.:	T-2	Depth:	3.75'-11.5'		The Hampshire Companies, LLC
COUNTY/MI	JNICIPALITY	Essex			BLOCK		LOT			
1. Test Num	ber	11	_Replicate (	letter)	В	_ Date Col	llected	1/16/2015		
2. Material	Fested:		_Fill .	Х	Test in N	lative Soil				
3. Type of S	Sample:	X	_ Undisturbe	d		Disturbe	d			
4. Sample E	Dimensions:		Inside Radi Length of S			R, in cm	1.91 2.25			
5. Bulk Den	sity Determina	tion (Distu	bed Samples	Only): N	'A					
6. Sample V	Veight (Wt. Tu	be Contair	ing Sample-\	Wt. of Empt	y Tube), g	grams	0.00	- <del>-</del>		Wt. of Tube Containing Sample Wt. of Empty Tube
7. Sample \	olume (L x 2.5	54 cm./inch	x 3.14R2), c	c.			65.12	<del></del>		
8. Bulk Den	sity (Sample V	Vt./Sample	Volume), gra	ms/cc.			0	> 1.2		
9. Standpip	e Used:	Х	_No		Yes, Inc	dicate Inter	nal Radius,	cm. N/A		
10. Height o	of Water Level	Above Rin	n of Test Basi	n, in inches	3:					
11 Pate of	At the Begin At the End of Water Level D	f Each Tes	Interval, H2		4.6					
II. Rate of	Time, Sta	rt of Test val, T1	Time En	d of Test val T2	Leng	th of Test , T, Minute	s			
						16.00				
						16.67				
						47.83	_			
12 Calcula	tion of Permea	ibility:	K (in/hr) =	60 min/hr	r2/R2 x I	(in)/T(min)	 ) x ln (H1/H2	r) T=	46.83	
12. 0010010	K (in/hr) =	0.70	.,,,,	Classifica		K2	`	•		
13. Defects	in the Sample	(Check ap	— propriate iter	ns):						
		None	•	,						
	S	-	ontact	Large G	Fravel		Large Ro	oots		
			Sn							
		,								
		ther - Spec	JI Y							

Other - Specify \_

Project: Proposed Mountainside Hospital Redevelopment
Client: The Hampshire Companies, LLC 2.5'-4.0' SPP-2 T-1 Depth: Sample ID: Profile Pit No.: Sample No.: Lab Tech: DO BLOCK LOT COUNTY/MUNICIPALITY Essex \_\_\_\_ A \_\_ Date Collected 1/16/2015 Replicate (letter) 1. Test Number X Test in Native Soil 2. Material Tested: Fill Disturbed Х 3. Type of Sample: Undisturbed Inside Radius of Sample Tube, R, in cm 4. Sample Dimensions: Length of Sample, L, in inches 5. Bulk Density Determination (Disturbed Samples Only): N/A Wt. of Tube Containing Sample \_ 6. Sample Weight (Wt. Tube Containing Sample-Wt. of Empty Tube), grams 0.00 Wt. of Empty Tube 7. Sample Volume (L x 2.54 cm./inch x 3.14R2), cc. 86.83 0 > 1.2 8. Bulk Density (Sample Wt./Sample Volume), grams/cc. Yes, Indicate Internal Radius, cm. N/A 9. Standpipe Used: \_\_\_\_X\_\_\_No 10. Height of Water Level Above Rim of Test Basin, in inches: At the Beginning of Each Test Interval, H1 4.63 4.51 At the End of Each Test Interval, H2 11. Rate of Water Level Drop (Add additional lines if needed): Length of Test Time, Start of Test Time End of Test Interval, T, Minutes Interval, T1 Interval T2 144.83 12. Calculation of Permeability: K,  $(in/hr) = 60 \text{ min/hr} \times r^2/R^2 \times L(in)/T(min) \times ln (H1/H2)$  T= 144.83 Classification: K (in/hr) = 0.03 13. Defects in the Sample (Check appropriate items): None \_\_\_\_\_ Large Roots Soil/Tube Contact \_\_\_\_ \_\_\_Large Gravel \_\_\_\_ Dry Soil \_\_\_\_\_Smearing \_\_\_\_ Compaction

Sample ID:	Profile Pit No.:	SPP-2 Samp	ele No.: <u>T-1</u>	Depth:	2.5'-4.0'		Proposed Mountainside Hospital Redevelopme The Hampshire Companies, LLC DO
COUNTY/MUN	IICIPALITY Essex		BLOCK	LOT			
1. Test Number	r <u>1</u>	Replicate (letter)	B Date Co	ollected	1/16/2015		
2. Material Tes	sted:	FillX	_ Test in Native Soil				
3. Type of San	nple: X	Undisturbed	Disturb	ed			
4. Sample Dim	nensions:	Inside Radius of Sam Length of Sample, L,		1.91 2.75			
5. Bulk Densit	y Determination (Dist	urbed Samples Only): 1	√/A				
6. Sample We	ight (Wt. Tube Conta	ining Sample-Wt. of Emp	oty Tube), grams	0.00	<del></del>		Wt. of Tube Containing Sample Wt. of Empty Tube
7. Sample Vol	ume (L x 2.54 cm./inc	h x 3.14R2), cc.		79.60	<del></del>		
8. Bulk Densit	y (Sample Wt./Sampl	e Volume), grams/cc.		0	> 1.2		
9. Standpipe U	Jsed: X	No	_ Yes, Indicate Inte	rnal Radius,	cm. N/A		
10. Height of V	Water Level Above Ri	m of Test Basin, in inche	es:				
	At the Beginning of Ea At the End of Each Te		4.63				
11. Rate of W	ater Level Drop (Add	additional lines if neede	d):				
	Time, Start of Test Interval, T1	Time End of Test Interval T2	Length of Test Interval, T, Minut				
			356.25				
-							
-							
L							
12. Calculation	n of Permeability:	K, (in/hr) = 60 min/hr	x r2/R2 x L(in)/T(mir	n) x ln (H1/H2	2) T=	356.25	
H	(in/hr) = 0.00	Classific	ation: K0				
13. Defects in	the Sample (Check a	ppropriate items):					
_	None						
	Soil/Tube (	ContactLarge	Gravel	Large Ro	oots		
-	Dry Soil	Smearing	Comp	action			
	Other - Spe	ecify					

Project: Proposed Mountainside Hospital Redevelopment Sample No.: Sample ID: Profile Pit No.: SPP-2 T-2 Depth: 4.0'-10.0' Client: The Hampshire Companies, LLC Lab Tech: DO BLOCK LOT COUNTY/MUNICIPALITY Essex Replicate (letter) A Date Collected 1/16/2015 1. Test Number X Test in Native Soil 2. Material Tested: Fill Disturbed 3. Type of Sample: Undisturbed Inside Radius of Sample Tube, R, in cm 4. Sample Dimensions: Length of Sample, L, in inches 5. Bulk Density Determination (Disturbed Samples Only): N/A Wt. of Tube Containing Sample 6. Sample Weight (Wt. Tube Containing Sample-Wt. of Empty Tube), grams 0.00 Wt. of Empty Tube 7. Sample Volume (L x 2.54 cm./inch x 3.14R2), cc. 94.07 0 > 1.2 8. Bulk Density (Sample Wt./Sample Volume), grams/cc. Yes, Indicate Internal Radius, cm. N/A \_\_\_\_X\_\_\_No 9. Standpipe Used: 10. Height of Water Level Above Rim of Test Basin, in inches: At the Beginning of Each Test Interval, H1 At the End of Each Test Interval, H2 11. Rate of Water Level Drop (Add additional lines if needed): Time, Start of Test Time End of Test Length of Test Interval, T, Minutes Interval, T1 Interval T2 103.34 98.00 98.75 12. Calculation of Permeability: K,  $(in/hr) = 60 \text{ min/hr} \times r2/R2 \times L(in)/T(min) \times ln (H1/H2)$  T= 100.03 K (in/hr) = 0.41 Classification: K1 13. Defects in the Sample (Check appropriate items): None Soil/Tube Contact \_\_\_\_ \_\_\_Large Gravel \_\_\_\_ \_\_\_ Large Roots Dry Soil \_\_\_\_\_ Smearing \_\_\_\_ Compaction \_\_\_ Other - Specify \_\_

\_ Other - Specify \_

Project: Proposed Mountainside Hospital Redevelopment Client: The Hampshire Companies, LLC T-2 Depth: 4.0'-10.0' Sample ID: Profile Pit No.: SPP-2 Sample No.: Lab Tech: DO COUNTY/MUNICIPALITY Essex BLOCK LOT 1. Test Number \_\_\_Replicate (letter) B Date Collected 1/16/2015 2. Material Tested: \_\_\_\_X Test in Native Soil Fill Disturbed 3. Type of Sample: Х Undisturbed 4. Sample Dimensions: Inside Radius of Sample Tube, R, in cm 3.00 Length of Sample, L, in inches 5. Bulk Density Determination (Disturbed Samples Only): N/A Wt. of Tube Containing Sample \_\_ 6. Sample Weight (Wt. Tube Containing Sample-Wt. of Empty Tube), grams 0.00 Wt. of Empty Tube 7. Sample Volume (L x 2.54 cm./inch x 3.14R2), cc. 86.83 0 > 1.2 8. Bulk Density (Sample Wt./Sample Volume), grams/cc. \_\_\_\_X\_\_\_No Yes, Indicate Internal Radius, cm. N/A 9. Standpipe Used: 10. Height of Water Level Above Rim of Test Basin, in inches: At the Beginning of Each Test Interval, H1 At the End of Each Test Interval, H2 3.50 11. Rate of Water Level Drop (Add additional lines if needed): Length of Test Time, Start of Test Time End of Test Interval, T, Minutes Interval T2 Interval, T1 141.40 140.50 12. Calculation of Permeability: K,  $(in/hr) = 60 \text{ min/hr} \times r2/R2 \times L(in)/T(min) \times ln (H1/H2)$  T= \_\_\_140.95\_\_ K (in/hr) = \_\_\_\_\_0.32\_\_\_ Classification: K1 13. Defects in the Sample (Check appropriate items): \_\_\_ None \_\_\_Large Gravel \_\_\_\_\_ Large Roots \_\_\_ Soil/Tube Contact \_\_\_\_ \_\_\_ Dry Soil \_\_\_\_\_Smearing \_\_\_\_\_ Compaction

Sample ID:	Profile Pit No.:	SPP-3 S	ample No.: <u>T-1</u>	Depth:	1.0'-2.5'	Project: Proposed Mountainside Hospital Redevelopment Client: The Hampshire Companies, LLC Lab Tech: DO
COUNTY/M	UNICIPALITY Essex		BLOCK	LOT		242 730/11 20
1. Test Num	nber <u>1</u>	Replicate (letter)	A Date 0	Collected	1/16/2015	
2. Material	Tested:	Fill	Test in Native Sc	pil		
3. Type of	Sample: X	Undisturbed	Distur	bed		
4. Sample l	Dimensions:	Inside Radius of Length of Sample	Sample Tube, R, in cm e, L, in inches	1.91 3.00	 _	
5. Bulk Der	nsity Determination (Distr	irbed Samples Only	): N/A			
6. Sample	Weight (Wt. Tube Contai	ning Sample-Wt. of	Empty Tube), grams	0.00	<del></del>	Wt. of Tube Containing Sample Wt. of Empty Tube
7. Sample	Volume (L x 2.54 cm./incl	n x 3.14R2), cc.		86.83		
8. Bulk Der	nsity (Sample Wt./Sample	e Volume), grams/co		0	_ > 1.2	
9. Standpip	e Used: X	No	Yes, Indicate Int	ernal Radius,	cm. N/A	
10. Height	of Water Level Above Ri	m of Test Basin, in i	nches:			
	At the Beginning of Ea At the End of Each Tes		5.00 5.00			
11. Rate of	Water Level Drop (Add	additional lines if ne	eded):			
	Time, Start of Test Interval, T1	Time End of To Interval T2	est Length of Tes Interval, T, Minu			
			345.00			
				$\dashv$		
12. Calcula	tion of Permeability:	K, (in/hr) = 60 mi	n/hr x r2/R2 x L(in)/T(mi	in) x In (H1/H2	!) T=	345.00
	K (in/hr) =0.00	Class	sification: K(	0		
13. Defects	in the Sample (Check a	opropriate items):				
	None					
	Soil/Tube C	ontactLar	ge Gravel	Large Ro	oots	
	Dry Soil	Smearin	Comp	paction		
	Other - Spe	cify				

Other - Specify \_

Project: Proposed Mountainside Hospital Redevelopment
Client: The Hampshire Companies, LLC Profile Pit No.: SPP-3 T-1 Depth: 1.0'-2.5' Sample ID: Sample No.: Lab Tech: DO COUNTY/MUNICIPALITY Essex BLOCK LOT 1/16/2015 1 Replicate (letter) B Date Collected Fill X Test in Native Soil 2. Material Tested: 3. Type of Sample: Undisturbed Disturbed 4. Sample Dimensions: Inside Radius of Sample Tube, R, in cm Length of Sample, L, in inches 5. Bulk Density Determination (Disturbed Samples Only): N/A Wt. of Tube Containing Sample \_ 6. Sample Weight (Wt. Tube Containing Sample-Wt. of Empty Tube), grams 0.00 Wt. of Empty Tube 7. Sample Volume (L x 2.54 cm./inch x 3.14R2), cc. 86.83 8. Bulk Density (Sample Wt./Sample Volume), grams/cc. 0 > 1.2 \_\_\_\_X\_\_\_No Yes, Indicate Internal Radius, cm. N/A 9. Standpipe Used: 10. Height of Water Level Above Rim of Test Basin, in inches: At the Beginning of Each Test Interval, H1 At the End of Each Test Interval, H2 5.00 5.00 11. Rate of Water Level Drop (Add additional lines if needed): Time End of Test Time, Start of Test Length of Test Interval, T, Minutes Interval, T1 Interval T2 142.00 12. Calculation of Permeability: K,  $(in/hr) = 60 \text{ min/hr} \times r2/R2 \times L(in)/T(min) \times ln (H1/H2)$  T= 142.00 Classification: K (in/hr) = 0.00 13. Defects in the Sample (Check appropriate items): None Soil/Tube Contact \_\_\_\_\_Large Gravel \_\_\_\_\_Large Roots Dry Soil \_\_\_\_\_Smearing \_\_\_\_\_Compaction

Other - Specify \_\_\_

Project: Proposed Mountainside Hospital Redevelopment 2.5'-11.0' Client: The Hampshire Companies, LLC T-2 Depth: SPP-3 Sample No.: Sample ID: Profile Pit No.: Lab Tech: DO COUNTY/MUNICIPALITY Essex BLOCK LOT 1/16/2015 A Date Collected 1. Test Number 1 Replicate (letter) \_\_\_\_X \_\_\_ Test in Native Soil \_Fill 2. Material Tested: Disturbed X Undisturbed 3. Type of Sample: Inside Radius of Sample Tube, R, in cm 4. Sample Dimensions: 3.00 Length of Sample, L, in inches 5. Bulk Density Determination (Disturbed Samples Only): N/A Wt. of Tube Containing Sample 6. Sample Weight (Wt. Tube Containing Sample-Wt. of Empty Tube), grams 0.00 Wt. of Empty Tube 86,83 7. Sample Volume (L x 2.54 cm./inch x 3.14R2), cc. 0 > 1.2 8. Bulk Density (Sample Wt./Sample Volume), grams/cc. Yes, Indicate Internal Radius, cm. N/A \_\_\_\_X\_\_\_No 9. Standpipe Used: 10. Height of Water Level Above Rim of Test Basin, in inches: At the Beginning of Each Test Interval, H1 At the End of Each Test Interval, H2 11. Rate of Water Level Drop (Add additional lines if needed): Time End of Test Length of Test Time, Start of Test Interval, T, Minutes Interval T2 Interval, T1 22.84 26.10 25.00 29.42 25.84  $K_r$  (in/hr) = 60 min/hr x r2/R2 x L(in)/T(min) x ln (H1/H2) T=12. Calculation of Permeability: Classification: K (in/hr) = 1.65 13. Defects in the Sample (Check appropriate items): None Soil/Tube Contact \_\_\_\_\_Large Gravel \_\_\_\_\_ Large Roots \_\_\_ Dry Soil \_\_\_\_\_Smearing \_\_\_\_ Compaction

\_\_\_ Other - Specify \_\_\_

Project: Proposed Mountainside Hospital Redevelopment
Client: The Hampshire Companies, LLC SPP-3 Sample No.: 2.5'-11.0' Profile Pit No.: T-2 Depth: Sample ID: Lab Tech: DO BLOCK LOT COUNTY/MUNICIPALITY Essex B Date Collected 1/16/2015 Replicate (letter) 1. Test Number Test in Native Soil 2. Material Tested: Fill Disturbed 3. Type of Sample: X Undisturbed Inside Radius of Sample Tube, R, in cm 4. Sample Dimensions: Length of Sample, L, in inches 3.00 5. Bulk Density Determination (Disturbed Samples Only): N/A Wt. of Tube Containing Sample 6. Sample Weight (Wt. Tube Containing Sample-Wt. of Empty Tube), grams 0.00 Wt. of Empty Tube 7. Sample Volume (L x 2.54 cm./inch x 3.14R2), cc. 86.83 0 > 1.2 8. Bulk Density (Sample Wt./Sample Volume), grams/cc. Yes, Indicate Internal Radius, cm. N/A \_\_\_\_X\_\_\_No 9. Standpipe Used: 10. Height of Water Level Above Rim of Test Basin, in inches: At the Beginning of Each Test Interval, H1 3.75 At the End of Each Test Interval, H2 11. Rate of Water Level Drop (Add additional lines if needed): Time, Start of Test Time End of Test Length of Test Interval, T, Minutes Interval, T1 Interval T2 102.50 102.50 104.00 105.25 K,  $(in/hr) = 60 \text{ min/hr} \times r2/R2 \times L(in)/T(min) \times ln (H1/H2)$  T = 103.56 12. Calculation of Permeability: K1 K (in/hr) = 0.41 Classification: 13. Defects in the Sample (Check appropriate items): \_\_\_\_\_Large Roots \_\_Soil/Tube Contact \_\_\_\_ \_\_\_Large Gravel \_\_\_ Dry Soil \_\_\_\_\_Smearing \_\_\_\_\_Compaction

Sample ID:	Profile Pit No.:	SPP-4 Sar	mple No.: <u>T-1</u>	Depth:	1.5'-3.0'	Project: Proposed Mountainside Hospital Redevelopment Client: The Hampshire Companies, LLC Lab Tech: DO
COUNTY/MI	UNICIPALITY Essex		BLOCK	LOT		<b>243 (66)</b> 36
1. Test Num	ber <u>1</u>	Replicate (letter)	A Date Co	ollected	1/16/2015	
2. Material	Tested:	_FillX	Test in Native Soil			
3. Type of S	Sample: X	Undisturbed	Disturbe	ed		
4. Sample E	Dimensions:	Inside Radius of S Length of Sample,	ample Tube, R, in cm L, in inches	1.91 2.75	_ _	
5. Bulk Den	sity Determination (Distu	rbed Samples Only):	N/A			
6. Sample V	Veight (Wt. Tube Contain	ning Sample-Wt. of E	mpty Tube), grams	0.00	_	Wt. of Tube Containing Sample Wt. of Empty Tube
7. Sample V	olume (L x 2.54 cm./inch	x 3.14R2), cc.		79.60		
8. Bulk Den	sity (Sample Wt./Sample	Volume), grams/cc.		0	> 1.2	
9. Standpip	e Used: X	No	Yes, Indicate Inte	rnal Radius, c	m. N/A	
10. Height of	of Water Level Above Rin	n of Test Basin, in inc	ches:			
	At the Beginning of Each At the End of Each Tes		4.75 4.50			
11. Rate of	Water Level Drop (Add a	additional lines if need	ied):			
	Time, Start of Test Interval, T1	Time End of Tes Interval T2	Length of Test Interval, T, Minute	es		
			140.00			
12. Calculat	tion of Permeability:	K, (in/hr) = 60 min/	hr x r2/R2 x L(in)/T(min	) x ln (H1/H2)	) T= _	140.00
	K (in/hr) =0.06	Classit	ication: K0			
13. Defects	in the Sample (Check ap	ppropriate items):				
	None					
	Soil/Tube Co	ontactLarg	e Gravel	Large Ro	ots	
	Dry Soil	Smearing	Compa	action		
	Other - Spec	cify				

Tube Permeameter Test Data								GJ1413224.000
Sample ID:	Profile Pit No.:	SPP-4	Sample No.:	T-1	_Depth:	1.5'-3.0'	Client:	Proposed Mountainside Hospital Redevelopment The Hampshire Companies, LLC
COUNTY/MUNIC	IPALITY Essex		BLOCK		_LOT		Lab Tech:	50
1. Test Number	1	Replicate (le	tter) B	Date Coll	ected	1/16/2015		
2. Material Teste	d:	Fi8	X Test in I	Native Soil				
3. Type of Sampl	le: X	Undisturbed		Disturbed	i			
4. Sample Dimen	nsions:		s of Sample Tube, mple, L, in inches	R, in cm	1.91 3.00	<u> </u>		
5. Bulk Density D	Determination (Distu	rbed Samples (	Only): N/A					
6. Sample Weigh	nt (Wt. Tube Contair	ning Sample-Wi	t. of Empty Tube),	grams	0.00	<del></del>		Wt. of Tube Containing Sample Wt. of Empty Tube
7. Sample Volum	ne (L x 2.54 cm./inch	x 3.14R2), cc.			86.83			
8. Bulk Density (	Sample Wt./Sample	Volume), gram	s/cc.		0	> 1.2		
9. Standpipe Use	ed: X	No	Yes, In	dicate Intern	al Radius,	cm. N/A		
10. Height of Wa	iter Level Above Rin	n of Test Basin,	in inches:					
	he Beginning of Eac he End of Each Tes		H1 4.5					
11. Rate of Wate	er Level Drop (Add a	dditional lines i	f needed):					
•	Time, Start of Test Interval, T1	Time End Interval		th of Test , T, Minutes				
			1	40.00				
					_			
					_			
					_			
12. Calculation o	of Permeability:	K, (in/hr) = 6	0 min/hr x r2/R2 x	_(in)/T(min)	x In (H1/H2	?) T= _	140.00	
K (ii	n/hr) = 0.03	_ c	lassification:	K0				
13. Defects in the	e Sample (Check ap	propriate items	):					
	None							
MANAGEM AT	Soil/Tube Co	ontact	_Large Gravel		_ Large Ro	oots		
THE PARTY NAMED IN COLUMN TO THE PARTY NAMED	Dry Soil	Sme	aring	Compac	tion			
	Other - Spec	ify						

Sample ID:	Profile Pit No.:	SPP-4	Sample No.:	T-2 Depth:	3.0'-8.0'	Project: Proposed Mountainside Hospital Redevelopmen Client: The Hampshire Companies, LLC Lab Tech: DO
COUNTY/M	UNICIPALITY Essex		BLOCK	LOT	-	Lab Tech. DO
1. Test Num	ber 1	Replicate (lette	er) <u>B</u> [	Date Collected	1/16/2015	
2. Material	Tested:	Fill	X Test in Nati	ive Soil		
3. Type of S	Sample: X	Undisturbed	[	Disturbed		
4. Sample E	Dimensions:		of Sample Tube, R, i ple, L, in inches	in cm 1.9° 2.00		
5. Bulk Den	sity Determination (Dis	turbed Samples Or	ly): N/A			
6. Sample V	Veight (Wt. Tube Conta	aining Sample-Wt.	of Empty Tube), gra	ms <u>0.00</u>	)	Wt. of Tube Containing Sample Wt. of Empty Tube
7. Sample V	/olume (L x 2.54 cm./in	ch x 3.14R2), cc.		57.8	9	W. or Empty rube
8. Bulk Den	sity (Sample Wt./Samp	le Volume), grams/	cc.	0	> 1.2	
9. Standpipe	e Used: X	No	Yes, Indica	ate Internal Radius	s, cm. N/A	
10. Height of	of Water Level Above R	tim of Test Basin, in	n inches:			
	At the Beginning of E At the End of Each Te		11 <u>4.75</u> 3.75			
11. Rate of	Water Level Drop (Add	additional lines if r	needed):			
	Time, Start of Test Interval, T1	Time End of Interval T				
			32.7	75		
			35.3	34		
			32.3	33		
			32.5	50		
12. Calculat	tion of Permeability:	K, (in/hr) = 60 i	min/hr x r2/R2 x L(in	)/T(min) x ln (H1/l	H2) T= _	33.23
	K (in/hr) = 0.85	Cla	ssification:	K2		
13. Defects	in the Sample (Check a	appropriate items):				
	None					
	Soil/Tube (	ContactL	arge Gravel	Large F	Roots	
	Dry Soil	Smear	ing	Compaction		
	Other - Spe	ecify				

Other - Specify \_\_\_\_

Project: Proposed Mountainside Hospital Redevelopment SPP-4 Sample No.: T-2 Depth: 3.0'-8.0' Client: The Hampshire Companies, LLC Profile Pit No.: Sample ID: Lab Tech: DO BLOCK LOT COUNTY/MUNICIPALITY Essex \_\_\_\_ C \_\_ Date Collected 1 Replicate (letter) 1/16/2015 1. Test Number Fill X Test in Native Soil 2 Material Tested: 3. Type of Sample: Undisturbed \_\_\_ Disturbed Inside Radius of Sample Tube, R, in cm Length of Sample, L, in inches 4. Sample Dimensions: 5. Bulk Density Determination (Disturbed Samples Only): N/A Wt. of Tube Containing Sample \_\_ 6. Sample Weight (Wt. Tube Containing Sample-Wt. of Empty Tube), grams 0.00 Wt. of Empty Tube 65.12 7. Sample Volume (L x 2.54 cm./inch x 3.14R2), cc. 8. Bulk Density (Sample Wt./Sample Volume), grams/cc. \_\_\_\_0 > 1.2 Yes, Indicate Internal Radius, cm. N/A \_\_\_\_X\_\_\_No 9. Standpipe Used: 10. Height of Water Level Above Rim of Test Basin, in inches: At the Beginning of Each Test Interval, H1 At the End of Each Test Interval, H2 4.00 11. Rate of Water Level Drop (Add additional lines if needed): Time, Start of Test Time End of Test Length of Test Interval, T1 Interval T2 Interval, T, Minutes 32.25 32.33 33.17 33.10 12. Calculation of Permeability: K,  $(in/hr) = 60 \text{ min/hr} \times r2/R2 \times L(in)/T(min) \times ln (H1/H2)$  T= 32.71 K (in/hr) = 0.92 Classification: K2 13. Defects in the Sample (Check appropriate items): \_\_\_None \_\_\_\_Soil/Tube Contact \_\_\_\_\_Large Gravel \_\_\_\_\_ \_\_\_ Large Roots \_\_\_\_ Dry Soil \_\_\_\_\_\_Smearing \_\_\_\_\_ Compaction

\_\_\_ Other - Specify \_\_\_

Project: Proposed Mountainside Hospital Redevelopment
Client: The Hampshire Companies, LLC Sample ID: Profile Pit No.: SPP-5 Sample No.: T-1 Depth: 0.3'-8.0' Lab Tech: DO LOT BLOCK COUNTY/MUNICIPALITY Essex \_\_\_\_A Date Collected Replicate (letter) 1/16/2015 1. Test Number X Test in Native Soil 2. Material Tested: Fill Disturbed 3. Type of Sample: \_\_\_ Undisturbed Inside Radius of Sample Tube, R, in cm 4. Sample Dimensions: Length of Sample, L, in inches 5. Bulk Density Determination (Disturbed Samples Only): N/A 6. Sample Weight (Wt. Tube Containing Sample-Wt. of Empty Tube), grams 0.00 Wt. of Tube Containing Sample \_\_\_ Wt. of Empty Tube 7. Sample Volume (L x 2.54 cm./inch x 3.14R2), cc. 79.60 0 > 1.2 8. Bulk Density (Sample Wt./Sample Volume), grams/cc. Yes, Indicate Internal Radius, cm. N/A \_\_\_\_X\_\_\_No 9. Standpipe Used: 10. Height of Water Level Above Rim of Test Basin, in inches: At the Beginning of Each Test Interval, H1 5.00 At the End of Each Test Interval, H2 4.50 11. Rate of Water Level Drop (Add additional lines if needed): Length of Test Time, Start of Test Time End of Test Interval, T, Minutes Interval, T1 Interval T2 30.15 30.70 31.82 K,  $(in/hr) = 60 \text{ min/hr} \times r^2/R^2 \times L(in)/T(min) \times ln (H1/H2)$  T= 30.89 12. Calculation of Permeability: K (in/hr) = 0.56 Classification: K1 13. Defects in the Sample (Check appropriate items): None \_ Soil/Tube Contact \_\_\_\_ Large Roots \_\_\_Large Gravel \_\_\_ Dry Soil \_\_\_\_\_ Smearing \_\_\_\_ Compaction

Project: Proposed Mountainside Hospital Redevelopment Sample ID: Profile Pit No.: SPP-5 Sample No.: T-1 Depth: 0.3'-8.0' Client: The Hampshire Companies, LLC Lab Tech: DO COUNTY/MUNICIPALITY Essex BLOCK LOT 1. Test Number Replicate (letter) C Date Collected 1/16/2015 2. Material Tested: Fill X Test in Native Soil 3. Type of Sample: Undisturbed \_\_ Disturbed 4. Sample Dimensions: Inside Radius of Sample Tube, R, in cm 1.91 Length of Sample, L, in inches 3.00 5. Bulk Density Determination (Disturbed Samples Only): N/A 6. Sample Weight (Wt. Tube Containing Sample-Wt. of Empty Tube), grams 0.00 Wt. of Tube Containing Sample \_ Wt. of Empty Tube 7. Sample Volume (L x 2.54 cm./inch x 3.14R2), cc. 86.83 8. Bulk Density (Sample Wt./Sample Volume), grams/cc. \_\_\_\_0 > 1.2 \_\_\_\_X\_\_\_No 9. Standpipe Used: Yes, Indicate Internal Radius, cm. N/A 10. Height of Water Level Above Rim of Test Basin, in inches: At the Beginning of Each Test Interval, H1 At the End of Each Test Interval, H2 5.00 4.50 11. Rate of Water Level Drop (Add additional lines if needed): Time, Start of Test Time End of Test Length of Test Interval, T1 Interval T2 Interval, T, Minutes 37.20 38.17 39.37 12. Calculation of Permeability: K,  $(in/hr) = 60 \text{ min/hr} \times r2/R2 \times L(in)/T(min) \times ln (H1/H2)$ 38.25 K (in/hr) = \_\_\_\_\_0.50 Classification: 13. Defects in the Sample (Check appropriate items): \_ None \_\_\_Large Gravel \_\_\_ \_\_ Soil/Tube Contact \_\_\_\_ \_\_\_\_ Large Roots Dry Soil \_\_\_\_\_Smearing \_\_\_\_\_ Compaction Other - Specify \_\_\_

APPENDIX C
Supplemental Information
(USCS, Terms and Symbols)



35 TECHNOLOGY DRIVE
WARREN, NJ 07059
908.668.7777
FAX 908.754.5936
www.whitestoneassoc.com

### **UNIFIED SOIL CLASSIFICATION SYSTEM**

SOIL CLASSIFICATION CHART

	MAJOR DIVISIONS		LETTER SYMBOL	TYPICAL DESCRIPTIONS
	GRAVEL AND	CLEAN GRAVELS	GW	WELL-GRADED GRAVELS, GRAVEL-SAND MIXTURES, LITTLE OR NO FINES
	GRAVELLY SOILS	(LITTLE OR NO FINES)	GP	POORLY-GRADED GRAVELS, GRAVEL- SAND MIXTURES, LITTLE OR NO FINES
COARSE GRAINED SOILS	MORE THAN 50% OF COARSE	GRAVELS WITH FINES	GM	SILTY GRAVELS, GRAVEL-SAND-SILT MIXTURES
	FRACTION RETAINED ON NO. 4 SIEVE	(APPRECIABLE AMOUNT OF FINES)	GC	CLAYEY GRAVELS, GRAVEL-SAND-CLAY MIXTURES
	SAND AND SANDY	CLEAN SAND (LITTLE OR NO	sw	WELL-GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES
	SOILS	FINES)	SP	POORLY-GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES
MORE THAN 50% OF MATERIAL IS	MORE THAN 50% OF COARSE	SANDS WITH FINES	SM	SILTY SANDS, SAND-SILT MIXTURES
LARGER THAN NO. 200 SIEVE SIZE	FRACTION <u>PASSING</u> NO. 4 SIEVE	(APPRECIABLE AMOUNT OF FINES)	SC	CLAYEY SANDS, SAND-CLAY MIXTURES
FINE	SILTS	LIQUID LIMITS	ML	INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS OR CLAYEY SILTS WITH SLIGHT PLASTICITY
GRAINED SOILS	AND CLAYS	LESS THAN 50	CL	INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS
			OL	ORGANIC SILTS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY
MORE THAN 50% OF MATERIAL IS			МН	INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SAND OR SILTY SOILS
SMALLER THAN NO. 200 SIEVE SIZE	SILTS AND CLAYS	LIQUID LIMITS GREATER THAN 50	СН	INORGANIC CLAYS OF HIGH PLASTICITY, FAT CLAYS
			ОН	ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS
H	HIGHLY ORGANIC SOILS		PT	PEAT, HUMUS, SWAMP SOILS WITH HIGH ORGANIC CONTENTS

NOTE: DUAL SYMBOLS ARE USED TO INDICATE BORDERLINE SOIL CLASSIFICATIONS FOR SAMPLES WITH 5% TO 12% FINES

GRADATION*	COMPACTNESS* Sand and/or Gravel	CONSISTENCY* Clay and/or Silt		
% FINER BY WEIGHT	RELATIVE DENSITY	RANGE OF SHEARING STRENGTH IN POUNDS PER SQUARE FOOT		
TRACE	LOOSE	VERY SOFT LESS THAN 250 SOFT		

<sup>\*</sup> VALUES ARE FROM LABORATORY OR FIELD TEST DATA, WHERE APPLICABLE. WHEN NO TESTING WAS PERFORMED, VALUES ARE ESTIMATED.

j whitestn\geoforms\uscs.geo

Other Office Locations:

■ CHALFONT, PA 215.712.2700

STERLING, VA 703.464.5858 EVERGREEN, CO 303.670.6905



35 TECHNOLOGY DRIVE
WARREN, NJ 07059
908.668.7777
FAX 908.754.5936
www.whitestoneassoc.com

#### GEOTECHNICAL TERMS AND SYMBOLS

#### SAMPLE IDENTIFICATION

The Unified Soil Classification System is used to identify the soil unless otherwise noted.

#### SOIL PROPERTY SYMBOLS

- N: Standard Pentration Value: Blows per ft. of a 140 lb. hammer falling 30" on a 2" O.D. split-spoon.
- Qu: Unconfined compressive strength, TSF.
- Qp: Penetrometer value, unconfined compressive strength, TSF.
- Mc: Moisture content, %.
- LL: Liquid limit, %.
- PI: Plasticity index, %.
- δd: Natural dry density, PCF.
- ▼: Apparent groundwater level at time noted after completion of boring.

#### DRILLING AND SAMPLING SYMBOLS

- NE: Not Encountered (Groundwater was not encountered).
- SS: Split-Spoon 1 %" I.D., 2" O.D., except where noted.
- ST: Shelby Tube 3" O.D., except where noted.
- AU: Auger Sample.
- OB: Diamond Bit.
- CB: Carbide Bit
- WS: Washed Sample.

#### RELATIVE DENSITY AND CONSISTENCY CLASSIFICATION

#### <u>Term (Non-Cohesive Soils)</u> <u>Standard Penetration Resistance</u>

Very Loose	0-4
Loose	4-10
Medium Dense	10-30
Dense	30-50
Very Dense	Over 50

#### Term (Cohesive Soils) Qu (TSF)

Very Soft	0 - 0.25
Soft	0.25 - 0.50
Firm (Medium)	0.50 - 1.00
Stiff	1.00 - 2.00
Very Stiff	2.00 - 4.00
Hard	4.00+

#### PARTICLE SIZE

Boulders	8 in.+	Coarse Sand	5mm-0.6mm	Silt	0.074mm-0.005mm
Cobbles	8 in3 in.	Medium Sand	0.6mm-0.2mm	Clay	-0.005mm
Gravel	3 in -5mm	Fine Sand	0.2mm=0.074mm		

L:\Geotechnical Forms and References\TRMSSYM.wpd

Other Office Locations:

CHALFONT, PA 215.712.2700 STERLING, VA 703,464.5858 EVERGREEN, CO 303.670.6905